

Jan 6 '59

ENGINEERING
LIBRARY

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

DECEMBER 1958



VOL. LIII. NO. 12

FIFTY-THIRD YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Unnecessary Accuracy	413
Shrinkage Stresses in Composite Floors	415
<i>By R. J. Bartlett</i>	415
Book Reviews	419
Hangar with Prestressed Roof at Abingdon	421
A Concrete and Glass Canopy	424
Large Water Tower at Dunstable	425
Petrol Storage Tanks in London	427
A Swiss System of Prestressing	431
Additional B.S. Loadings	441
A Dome at Dallas, Texas, U.S.A.	443
New Type of Long-span Roof	445
INDEX TO VOLUME LIII.	

No. 613

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

For Catalogue of "Concrete Series" books on
concrete and allied subjects, send a postcard to:

INDEX OF ADVERTISERS

	Page		Page
A.B. MOULD & CONSTRUCTION CO. LTD.	xlv	LAFARGE ALUMINOUS CEMENT CO. LTD.	xliii
ABELSON & CO. (ENGINEERS) LTD.	xliii	LAWES & SON (STAINES) LTD.	xxx
A.C.E. MACHINERY LTD.	—	LEEDS OIL & GREASE CO.	xxxvi
AIRSCREW & JICWOOD LTD.	xxix	LENSCRETE LTD.	xxxvi
ALLAM, E. P., & CO., LTD.	li	LILLINGTON, GEORGE, & CO. LTD.	xx
BANBERGERS LTD.	—	LIND, PETER, & CO. LTD.	vi
BORSARI CO.	xxv	McCALL & CO. (SHEFFIELD) LTD.	xlii
BOYER, WM., & SONS LTD.	xlii	McCALLS MACALLOY LTD.	xlii
B.R.C. ENGINEERING CO. LTD.	lxiv	MARLEY CONCRETE LTD.	—
BRITISH FOPES LTD.	—	MAY & BUTCHER LTD.	v
BRITISH STEEL PILING CO. LTD.	lv	MICANITE & INSULATORS CO. LTD.	—
BRITISH VISCEREN LTD.	xiii	MILBANK FLOORS LTD.	xxxii
BYRD, A. A., & CO. LTD.	—	MILLS SCAFFOLD CO. LTD.	—
CAPLIN ENGINEERING CO. LTD.	xxx	MODULAR CONCRETE CO. LTD.	xxiiii
CEMENT MARKETING CO. LTD.	xxiv	MONK, A., & CO. LTD.	xi
CEMENT & STEEL LTD.	iv	MORAN, WHITLEY, & CO. LTD.	—
CLEMENTATION CO. LTD.	xvii	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	xliii
C.E.T. (PLANT) LTD.	—	OMNIA CONSTRUCTIONS LTD.	—
CHAPMAN, H. W., LTD.	xliii	PASHLEY & TRICKETT LTD.	—
CHEETHAM, ALEX J., LTD.	xxiv	PORTASILO LTD.	—
CHEMICAL BUILDING PRODUCTS LTD.	—	PRIEST, B., & SONS LTD.	xi
CHRISTIANI & NIELSEN LTD.	—	PRODORITE LTD.	—
CIVIL ENGINEERING PLANT LTD.	xxvi	P.S.C. EQUIPMENT LTD.	vi
CONCRETE LTD.	xxvii	PYNFORD LTD.	—
COLVILLES LTD.	—	RANALAH STEEL MOULDS LTD.	—
CONCRETE LTD.	—	RAWPLUG CO. LTD.	xxxiv
CONCRETE EQUIPMENT & METAL PRODUCTS (WESTMINSTER) LTD.	—	ROAD MACHINES (DRAYTON) LTD.	—
CONCRETE PILING LTD.	—	ROVER CAR CO. LTD.	—
CONCRETE PROOFING CO. LTD.	xxxiv	RUBEROID CO. LTD.	xxviii
CONCRETE PUMP CO. LTD.	xxxiii	RUSH & TOMPKINS LTD.	—
CONCRETE SERVICES LTD.	xix	RYLANDS BROTHERS LTD.	—
CORNELLY EQUIPMENT CO. LTD.	—	SANKEY, J. H., & SON LTD.	—
DAVIDSON, C., & SONS LTD.	—	SIMON-CARVES LTD.	is
DEMOLITION & CONSTRUCTION CO. LTD.	viii	SIMPLEX CONCRETE PILES LTD.	lvii
DEMOLITION, SAML., & SON, LTD.	liii, lvi	SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.	xiv
DICKENS, STUART B., LTD.	—	STAINLESS STEEL WIRE CO. LTD.	xxx
DORMAN LONG (STEEL) LTD.	—	STELMO LTD.	liv
EVODE LTD.	—	STENT PRECAST CONCRETE LTD.	—
EXPANDITE LTD.	xlvii	STIC B PAINT SALES LTD.	—
FLEXIBLE DRIVE & TOOL CO. LTD.	xliii	STONE COURT BALLAST CO. LTD.	—
FORD MOTOR CO. LTD.	xxxi	STORER, WM. T., & CO. LTD.	xxvii
FORMCRETE LTD.	—	STOREY, THOS. (ENGINEERS) LTD.	—
FRANKI COMPRESSED PILE CO. LTD.	xxi	STUART'S GRANOLITHIC CO. LTD.	ii
GADD, GEORGE, & CO., LTD.	xviii	TECHNICAL PAINT SERVICES	—
G.K.N. REINFORCEMENTS LTD.	lviii	TELEHOIST LTD.	—
GINUTE CONSTRUCTION CO. LTD.	xlii	TENTOR BAR CO. LTD.	lviii
HILL, RICHARD, LTD.	—	TERRESEARCH LTD.	—
HILTON GRAVEL LTD.	—	THAMES PLYWOOD MANUFACTURERS LTD.	xvi
HOLLAND & HANNEN AND CUBITTS (Gt. BRITAIN) LTD.	—	THORNTON, WILLIAM, & SONS LTD.	—
HOLST & CO. LTD.	—	TRENT GRAVELS LTD.	44
HUNTLEY & SPARKS LTD.	lxii	UNI-TUBES LTD.	—
IMPERIAL CHEMICAL INDUSTRIES LTD.	—	VOLKMANN, O. A.	—
JOHNSON, RICHARD, & NEPHEW LTD.	xxii	WATES LTD.	—
JONES, T. C., & CO. LTD.	x	WELBECK TRADING CO. LTD.	—
KING, J. A., & CO. LTD.	xlii	WESTWOOD, JOSEPH, & CO. LTD.	xlviii
KWIKFORM LTD.	—	WHITEHEAD IRON & STEEL CO. LTD.	—
YORKSHIRE HENNEBIQUE CONCRETING CO. LTD.	—	WHITLEY MORAN & CO. LTD.	—

58.
Page
xlii
xxx
xxvi
xxvi
xx
vii
—
xii
xii
xxv
v
—
xxxi
xxii
xi
—
xlii
—
—
lvi
xl
vi
—
—
xiv
—
viii
—
—
in
lvii
xv
xx
liv
liv
—
vii
—
xi
—
iii
vi
iii
42
1
—
iv
iii

THE
are s
mag
calcu
the
are k
beca
proce
is fo

estim
and t
based
which
by ca
the re
age, a
beca
enoug
of the
and b
struct
exact
with
suppo

Appr
slab is
width
they a
calcul
useless

M

D

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LIII, No. 12.

LONDON, DECEMBER, 1958.

EDITORIAL NOTES

Unnecessary Accuracy.

THE uncertainties inherent in the design and construction of reinforced concrete are so many that for most structures little or no attempt is made to predict the magnitude or even the nature of all the stresses. Superficial and much simplified calculations are generally made which are known to ignore many factors and the results compared with the recommendations in a code of practice which are known to allow for such factors; that is the secondary effects may be ignored because they are included in the factor of safety. The justification for this procedure is that for many years it has resulted in satisfactory structures, and it is foolish not to take advantage of experience.

For example, in designing an ell-beam the effective breadth of the flange is estimated empirically, and the effective depths at midspan and at the supports and the amount of reinforcement required are obtained by simple calculations based on the resistance to bending and shearing of an assumed ideal material which bears little relation to concrete. The breadth of the rib is determined by calculating a nominal shearing stress, or by the space required to accommodate the reinforcement. No calculations are made of the stresses due to creep, shrinkage, torsion caused by unbalanced loading, or normal changes of temperature, because the working stresses recommended by codes and regulations are small enough to allow such secondary stresses to be present without danger. Because of these uncertainties, it is also rarely necessary to determine precisely the loads and bending moments acting on a structure. All except the simplest of concrete structures are statically indeterminate, generally to a very high degree. The exact distribution of the load imposed on a beam by a slab which is monolithic with it, or of the bending moments acting on a continuous beam with elastic supports of finite width, are difficult, and sometimes impossible, to calculate. Approximations are therefore used; it is assumed that the load imposed by the slab is uniformly distributed, and that the beam has rigid supports of infinitesimal width. The results of the calculations are approximate and conservative, and as they are generally based on nominal uniform loads, and are used in perfunctory calculations to determine the dimensions of the members, greater accuracy is useless.

Most engineers are fully aware of the futility of basing "exact" calculations

on inexact data, but the belief that approximate methods are unsafe or otherwise unsatisfactory is still sufficiently widespread to be the cause of much wasted time and effort. In a recent design for continuous beams of equal spans calculations were made to determine the bending moments corresponding to all possible combinations of live loads on adjacent and alternate spans. The greatest bending moments at the supports were then reduced by fifteen per cent., and the bending moments at midspan were adjusted accordingly. As would be expected, the results of this lengthy exercise in arithmetic were almost identical with those given by the approximate coefficients which are generally used. The confusion of arithmetical accuracy with good design generally results only in a waste of the designer's time, but more serious consequences may occur. For example, a small retaining wall was built some years ago at the side of a garage; the wall overturned and was re-built to the same design, which the designer had carefully checked. The re-built wall also overturned, the calculations were submitted to another engineer to check, and it was found that although the arithmetic was impeccable no allowance had been made for the weight of loaded lorries parked immediately behind the wall. It is evident that the designer was so absorbed in arithmetic that he lost sight of a basic requirement.

There can be few designers who have never found that attempts at apparent arithmetical precision have tended to cloud their engineering judgment. Most employers discourage unnecessary precision, which wastes time and money and does them no credit when such work is seen by others. Indeed, the shortage of skilled designers of which so much is heard could be more accurately described as a surplus of relatively unskilled ones; if all unnecessary drawing-office work were avoided it is possible that calculations and drawings would be made at the same speed as before the war and there would no longer be an unsatisfied demand for designers and detailers.

There are many less obvious examples of waste than those mentioned in the foregoing, and which are of much more frequent occurrence. The arithmetical processes involved in such methods of design as moment distribution are often pursued to an unnecessary degree of accuracy, simply because the mechanical nature of the work leads to a temporary suspension of thought. Lightly-loaded slabs may be analysed and the reinforcement calculated, when a little thought would show that the minimum reinforcement permitted by the code of practice would be more than sufficient. Also, restraint moments may be calculated by more or less complex methods for structures whose unimportance would justify the use of estimated values. Occasionally such labour is performed in the name of economy, but the number of designers who compare the savings of material achieved in this way with the cost of the time taken to make them is surprisingly small. Greater accuracy in necessary detailing would save a great detail of expense, particularly when mistakes are discovered at a late stage.

The increased cost of drawing-office work is frequently mentioned by older engineers, some of whom claim that the output per man to-day is very much less than what it was twenty years ago. The avoidance of unnecessary arithmetic is an obvious way of making up for the fewer hours now spent at the drawing board as a result of the shorter working week and the longer holidays enjoyed by most designers. As in industry, higher costs in a drawing-office can often be countered by labour-saving devices.

By R. J. BARTLETT.

In beams and slabs of composite construction stresses develop due to the differential shrinkage of the components. The topping is generally cast over precast beams and the two eventually act together structurally. The shrinkage of the topping will be partly resisted by the beams and stresses will therefore be present in the combined section.

Consider the construction shown in *Fig. 1*. If *X* were not bonded to *Y* it would shrink unhindered and no stress would occur. Let *s* represent the shortening per unit length. If this shrinkage were elastic a constant stress equal to *s*




Fig. 1.




Fig. 2.

times Young's modulus *E* would be present in *X*, as shown in the stress diagram in *Fig. 2(a)*. The total force *F* would be *s* \times *E* times the area of *X*. This force acts eccentrically on the composite section producing a distribution of stress as in *Fig. 2(b)*. Since, however, force *F* is not present, the stress due to it acting on *X* alone must be allowed for in *Fig. 2(b)*, producing the distribution shown in *Fig. 2(c)*. The final stresses at top and bottom of the composite member are respectively

$$c_1 = \frac{F}{A_x + A_y} + \frac{Fe}{Z_t} - \frac{F}{A_x} \quad \dots \quad \dots \quad \dots \quad \dots \quad (1)$$

$$c_4 = \frac{F}{A_x + A_y} - \frac{Fe}{Z_b} \quad \dots \quad \dots \quad \dots \quad \dots \quad (2)$$

in which *A_x* and *A_y* are the areas of *X* and *Y*, *Z_t* and *Z_b* are the section moduli of the combined areas *X* and *Y*, and *e* is the distance between the centre of area of *X* and the centre of area of *X* and *Y* combined. Since the concretes in *X* and *Y* are of different composition and maturity it is advisable to use a modular ratio of, say, 1.5 or 2 in calculating the properties of the combined section. The

stresses c_2 in X and c_3 in Y at their surfaces of contact may be obtained by proportion from *Fig. 2(c)*.

The moment Fe is constant throughout the whole of the beam and therefore there are no shearing stresses. At each end, however, the stresses due to bending are zero and increase to a maximum over a short distance. This distance cannot be determined precisely, but from the principle of St. Venant it may be considered to be equal to the depth d of the joist.

From *Fig. 2(c)* it is seen that, in order to maintain the stresses in X, a force P in the plane of contact and a moment M perpendicular to this plane are necessary [*Fig. 3(a)*], and these are supplied by Y at each end of the beam. Conversely, P and M may be found by considering the stresses in Y as being maintained at each end of the beam by X as in *Fig. 3(b)*. Thus P and M are calculated from

$$c_1 = \frac{Pe_1 - M}{Z_x} - \frac{P}{A_x} \quad \dots \quad \dots \quad \dots \quad \dots \quad (3)$$

$$c_2 = \frac{Pe_1 - M}{Z_x} + \frac{P}{A_x} \quad \dots \quad \dots \quad \dots \quad \dots \quad (4)$$

in which e_1 is the eccentricity of P , and Z_x is the section modulus of X. Similarly,

$$c_3 = \frac{Pe_2 + M}{Z_{yt}} + \frac{P}{A_y} \quad \dots \quad \dots \quad \dots \quad \dots \quad (5)$$

$$c_4 = \frac{Pe_2 + M}{Z_{yb}} - \frac{P}{A_y} \quad \dots \quad \dots \quad \dots \quad \dots \quad (6)$$

in which e_2 is the eccentricity of P , and Z_{yt} and Z_{yb} are the section moduli of Y. The solution of (5) and (6) is not essential but is a check on the solution of (3) and (4).

The force P is a horizontal shearing force in the plane of contact of X and Y




Fig. 3.





Fig. 4.

at each end of the beam over an area d times the breadth b of the plane of contact.

If F is likened to a prestressing force imposed on the combined section, the distribution of the bond and the bursting stresses due to P and M respectively would be approximately as shown in Fig. 4(a) and (b) ("Prestressed Concrete." By Y. Guyon. Pages 128/9).

Thus the average bond stress

$$u = \frac{P}{bd} \quad \dots \quad \dots \quad \dots \quad \dots \quad \dots \quad (7)$$

The maximum bond stress is probably 50 per cent. higher than the average since the distribution over the distance d is approximately parabolic.

The maximum tensile stress f tending to separate the beam from the topping, which would occur at the end face of the beam, may be calculated as follows from the approximate dimensions in Fig. 4(b). Area BHC representing the tensile stress must equal the area AGB representing compression. Also BHC is very nearly a triangle since line BH is almost straight. The distance between the centres of areas of BHC and AGB is approximately half the depth. Therefore

$$M = \text{area BHC} \times b \times KL = \frac{1}{2}f \frac{d}{4} \times b \times \frac{d}{2} = \frac{fbd^2}{16}.$$

$$\text{Thus } f = \frac{16M}{bd^2} \text{ (approximately)} \quad \dots \quad \dots \quad \dots \quad \dots \quad \dots \quad (8)$$

The stresses due to shrinkage throughout the beam can be high in some cases, but will be substantially reduced by creep in both the beam and the topping.

It is assumed in the foregoing that both concretes are capable of resisting the tensile stresses indicated in Fig. 2(c). The introduction of stirrups at each end to assist in resisting P and M would be unavailing if cracking occurred in the topping, since it would divide the beam into two so far as shrinkage stresses are concerned because these stresses are independent of the length of the beam.

Example.

A topping 2 in. thick is cast over and bonded to precast beams at 20-in. centres (Fig. 5), Young's modulus is 2×10^6 per square inch for the topping and 4×10^6 per square inch for the beams, and the shrinkage per unit length of the topping is 2×10^{-4} . Calculate the stresses, due to shrinkage of the topping, in the cross section and the bond and bursting stresses at each end of the composite beam. $A_x = 20 \times 2 = 40$ sq. in. $A_y = (6 \times 2 + 2 \times 2 \times 2) \times \text{modular ratio} = 40$ sq. in. The distance of the centre of gravity of the section from the bottom is

$$\frac{40 \times 7 + 2 \times 12 \times 3 + 2 \times 8 \times 1}{40 + 40} = 4.6 \text{ in.}$$

The moment of inertia of the section is

$$\frac{20 \times 2^3}{12} + 40 \times 2.4^2 + \frac{2 \times 2 \times 6^3}{12} + 2 \times 12 \times 1.6^2 + \frac{2 \times 4 \times 2^3}{12} + 2 \times 8 \times 3.6^2 = 589.87 \text{ in.}^4$$

$$Z_t = \frac{589.87}{3.4} = 173.5 \text{ in.}^3 \quad Z_b = \frac{589.87}{4.6} = 128.0 \text{ in.}^3$$

$$F = 2 \times 10^{-4} \times 2 \times 10^6 \times 2 \times 20 = 16,000 \text{ lb.}$$

$$Fe = 16,000 \times (3.4 - 1) = 38,400 \text{ in.-lb.}$$

Using equations (1) and (2),

$$c_1 = \frac{16,000}{80} + \frac{38,400}{173.5} - \frac{16,000}{40} = 21.5 \text{ lb. per square inch.}$$

$$c_4 = \frac{16,000}{80} - \frac{38,400}{128.0} = -100 \text{ lb. per square inch.}$$

(c_4 , being negative, is a tensile stress.)

By drawing the stress diagrams as shown in *Fig. 6* similar to those in *Fig. 2*, c_2 and c_3 may be calculated from the geometry of similar triangles. Thus $c_3 = (21.5 + 400 + 100) \frac{6}{8} - 100 = 291 \text{ lb. per square inch}$ and $c_2 = 291 - 400 = -109 \text{ lb. per square inch.}$

The true stresses in the beams are c_3 and c_4 each multiplied by the modular ratio 2; that is

Stress at top = $c_3 \times m = 291 \times 2 = 582 \text{ lb. per square inch compression.}$
Stress at bottom = $c_4 \times m = 100 \times 2 = 200 \text{ lb. per square inch tension.}$

To calculate P and M , $A_x = 40 \text{ sq. in.}$, $Z_x = 20 \times \frac{2^3}{6} = \frac{40}{3}$, and $e_1 = 1 \text{ in.}$





Fig. 5.



stresses are in lb per sq. in.

Fig. 6.

Therefore, using equations (3) and (4),

$$21.5 = \frac{P \times 1 - M}{40} - \frac{P}{40} \cdot \frac{3}{3}$$

$$109 = \frac{P \times 1 - M}{40} + \frac{P}{40} \cdot \frac{3}{3}$$

therefore $P = 1750$ lb. and $M = 880$ in.-lb.

By calculating Z_{yt} , Z_{yb} , and e_2 , and then solving (5) and (6), substantially similar values of P and M are obtained. Then, from (7) and (8), the average bond stress between the topping and the beam $u = \frac{1750}{2 \times 6} = 146$ lb. per square inch.

and the approximate bursting stress $f = \frac{16 \times 880}{2 \times 6^2} = 196$ lb. per square inch.

Book Reviews.

"The Building of T.V.A." By John H. Kyle. (The Louisiana State University Press, Baton Rouge, U.S.A. Price \$7.50.)

No attempt is made at giving technical details. The volume comprises mainly photographs of the dams, bridges, power stations built by the Tennessee Valley Authority since it was formed twenty-five years ago, with brief notes on each structure.

"Züblin-bau." (Stuttgart: J. G. Cotta'sche Buchhandlung Nachf. No price stated.)

THE Swiss family of Züblin were among the pioneers of reinforced concrete in Europe. In the year 1894 Eduard Züblin built a reinforced concrete loggia in Naples. In 1895 he became the licensee for the Hennebique system in Italy, where he built reinforced concrete factories and a large tank in the years 1896 and 1897, and in 1898 transferred his activities to Strasbourg. The sixtieth anniversary of the starting of the Züblin business is marked by the issue of this fascinating book, written by Wolf v. Niebelschütz, translated into masterly English by A. Laubenthal, and beautifully printed and bound in Germany. The earlier chapters deal with the development of reinforced concrete in the second half of last century, and the remainder is used to illustrate some of the structures built by Ed. Züblin A.G. in many countries of the world. The book is one of the best sources of information on the early development of reinforced concrete, and the illustrations, although depicting the work of one firm only, present a remarkable record of the variety of reinforced

and prestressed concrete structures built in this century. The size and daring of some of the structures built fifty or more years ago will surprise many who are familiar only with more recent concrete work.

"Composite Construction in Steel and Concrete." By I. M. Viest, R. S. Fountain, and R. C. Singleton. (London: McGraw-Hill Publishing Co., Ltd. Price £2 18s.)

METHODS of designing members of structural steel sections encased in concrete, together with formulæ, tables, and graphs, are given in accordance with the recommendations of the American Association of State Highway Officials. The book comprises 170 pages, and is mostly concerned with bridges.

"Bemessungsverfahren." By Benno and Helmut Löser. (Berlin: Wilhelm Ernst & Sohn. 1958. Price 22 D.M.)

THE 16th edition of this handbook on the design of reinforced concrete is in accordance with the latest codes of practice of the German-speaking countries.

In the section on bending of rectangular sections, tables are included for the stresses of 42,670 lb. and 49,780 lb. per square inch permitted for Austrian high-grade IV steel and Torstahl. The properties of special high-grade and cold-worked steels are discussed, and notes are given on Torstahl 40, 60 and 80 and the Czechoslovakian Roxor steel. There is also a section on glass-concrete floors and roofs.

Professor Brendel describes a method

which is claimed to give more accurate results than the usual trial-and-error calculations in the preliminary design of prestressed beams of any shape.

The recommendations of the codes are explained, including the ultimate-load method of design, and numerical examples are given. Many of the formulæ and tables are not directly applicable to British practice, but others are useful.

"Architects' Detail Sheets." Edited by E. D. Mills. (London: Iliffe & Sons, Ltd. Price 30s.)

THIS is the fourth selection to be published in book form of detail sheets from "The Architect & Building News". It comprises 96 scale drawings of architectural details and more than a hundred photographs of work in Great Britain and other countries. The details relate to fireplaces, fittings, staircases, walls, windows, and other features. Nearly all of the designs are unusual (called here "contemporary"). In many cases it would have been courteous to give the names of the engineers concerned with the work.

"German Standard Code of Practice DIN. 4224 : Design of Reinforced Concrete." (Berlin: Wilhelm Ernst & Sohn. Price 6 D.M.)

THE methods of design recommended in this new code are considered in "Der Stahlbetonbau," by Karl Kersten, which was reviewed in this journal for June 1958.

"Vorgespannter Beton." By A. Mehmel. (Berlin: Springer-Verlag. Price 17.40 D.M.)

THIS work on prestressed concrete is based on the author's lectures at the Technische Hochschule, Darmstadt. Constructional details of the more important systems are discussed, and notes are given on methods of supporting and fixing the steel and ducts, the tensioning procedure, forms of anchorage, and the protection of the steel against corrosion.

There are fully-worked numerical examples for a continuous beam for a footbridge with post-tensioned steel and for a roof beam with pre-tensioned steel.

"Rigid Frame Formulas." By A. Kleinlogel. (London: Crosby Lockwood & Son, Ltd. Price 90s.)

IN this translation of the new (twelfth)

edition of the well-known German "Rahmenformeln" eleven frames have been replaced by eleven new frames, including symmetrical triangular frames with tie-rods and various conditions at the ends of the diagonals, symmetrical and unsymmetrical fixed rectangular frames with hinged joints, and frames with hinged or fixed bases and with or without ties at various heights. Small improvements have been made in the remainder of the book, but apart from the new frames the contents are substantially as before.

Books Received.

"Barragens Abóbada: Fundações, Projeto Sobre Modelos e Observações dos Protótipos" (Results of investigations of the foundations of arch dams). By Manuel Rocha and J. Laginha Serafim.

"A Utilização de Modelos no Dimensionamento das Estruturas; Aplicações Diversas" (A comparison of analytical and experimental methods of design). By Manuel Rocha and J. Ferry Borges.

"Solos das Estradas" (Portuguese report presented to the International Road Congress Istanbul, 1955).

[Lisbon: Laboratorio Nacional de Engenharia Civil. Printed in the Portuguese language, with brief summaries in English. No prices stated.]

"Spannungen an Tunnelöffnungen mit rechteckigem Nutzquerschnitt und kreisbogenförmiger Überwölbung" (Stress Distribution Around Tunnel Openings). By Rudolf Hiltzsch.

"Inverkan av deformationer i väggar på bjälklagsläster och bjälklagsdeformationer vid flervåningshus" (Effects of Deformations of Walls in Multiple-Story Houses). By Av Henrik Nylander and Einar Eriksson.

"The Design of Reinforced Concrete." By Carl Forssell. [Stockholm: Royal Institute of Technology. No price stated.]

"Investigations of Bond between Reinforcement and Concrete." By P. O. Jonsson. [Stockholm: Swedish Cement and Concrete Research Institute. Price 8 kroner. Printed in English.]

"Types of Road Surfacing and Maintenance using Tar or Asphaltic Bitumen." Road Note No. 5. (London: H.M.S.O. Price 3s.)

"Field Studies of the Movement of Soil Moisture." Technical Paper No. 41. (London: Department of Scientific and Industrial Research. Price 6s.)

December, 1958.

Hangar with Prestressed Roof at Abingdon.

ROOF CAST ON THE FLOOR.

A METHOD not hitherto used in Great Britain is being used for the erection of the shell roofs and supporting columns for a hangar at Abingdon, Berks, for Transport Command of the Royal Air Force.

The requirements were set out by the Air Ministry, and selected contractors were invited to submit designs and tenders for construction in steel, aluminium alloy, or any type of concrete construction. Of six tenders submitted, one was

prestressed with eight cables; the inner wall is 5 in. thick and prestressed with nine cables; each cable comprises twelve wires of 0.276 in. diameter. The solid valley beams are 9 in. wide by 10 ft. deep, and are prestressed with fourteen cables each containing twelve wires of 0.276 in. diameter. The gable beams are prestressed with sixteen cables each containing twelve 0.276-in. wires; they are of inverted tee-shape 18 ft. deep, 9 in. wide




Fig. 1.—The Roof During Casting.

for aluminium construction, one for structural steel with an aluminium roof, one for prestressed precast concrete, and the others for prestressed concrete cast in place. The design described was selected because it was considered to satisfy the requirements of stability, appearance, time of erection, durability, and low maintenance costs, and was also 10 per cent. cheaper than the next lowest tender and 28 per cent. cheaper than the highest tender.

The hangar is divided into three bays, each of which has an area of 186 ft. by 110 ft., and is roofed by three barrel vaults supported by a column at each corner; the bays are connected by two link-bays each 36 ft. wide. The total uninterrupted floor area is 613 ft. by 103 ft.

The hollow edge-beams are 6 ft. 5 in. wide, 5 ft. 1 in. deep at the outer face and 10 ft. deep at the inner face. The bottom is 6 in. thick and is prestressed with six cables; the outer wall is 5 in. thick and

at the stems, and 2 ft. 6 in. wide at the bottom for a depth of 1 ft. 6 in.

The beams were prestressed from both ends, and a "walkie-talkie" radio was used to co-ordinate the work.

In each "shell" there are 106 Freyssinet cables, each comprising twelve 0.276-in. wires. The roofs are 3½ in. thick at the crown and 5 in. thick at the valleys.

The roofs were cast on the floor of the hangar, on which building paper was laid to prevent adhesion of the beams which were cast directly on the floor. Form-work travelling on bogies was used for casting each vault in several sections; as each section was completed the form-work was moved on to the next section, the completed sections resting on the buter beams and the valley beams. Fig. 1 shows two of the bays completed and the third being cast. A section through the roof is shown in Fig. 2.

Each roof weighs about 1400 tons, and




Fig. 2.—Part Cross Section Through Roof.

the method of lifting a bay and forming the columns is shown in *Figs. 3 to 6*. The columns are formed of precast T-shape blocks of reinforced concrete to form a hollow column 4 ft. 6 in. by 3 ft. 6 in. in cross section; 1000 of these blocks, each weighing half a ton, were precast on the site for the twelve columns of the hangar.

The roofs were first lifted to a height of 2 ft. 8 in. above ground level by means of hydraulic jacks at each side, care being taken to ensure that the roof did not deviate more than 1 in. from the level position; this operation took six hours, after which the blocks were inserted to form the columns as the roof was raised to its

final height of 46 ft. The hydraulic jacks each had a capacity of 200 tons.

When the roof had been raised high enough to accommodate another course of blocks, two of the jacks were locked and the other two retracted while two blocks were placed in position on opposite sides of the column. Before the blocks were inserted a layer of stiff 1 : 3 cement mortar was placed on top, the depth of $\frac{1}{8}$ in. being ensured by the use of a steel tray fixed to the top of the block. The jacks that had been retracted were then set under the new blocks and the lifting continued until the roof was high enough for the insertion of blocks at the other



Fig. 3.—Roof Fully Raised.

two sides. When the load was applied the mortar joints were compressed to a

thickness of $\frac{1}{2}$ in., and none of the mortar was squeezed out.

The columns were prestressed by fourteen Macalloy bars of $1\frac{1}{2}$ in. diameter, anchored to a foundation block below ground level and tensioned from the top after the space between the blocks had been filled with concrete. In Fig. 6 is shown the steel bracing used to stabilise the structure before tensioning the bars.

In the design a maximum wind velocity of 85 miles per hour was allowed for, and a maximum variation in temperature of 45 deg. Fahr. The compressive strengths of the concrete were specified to be 4000 lb. per square inch at 28 days in the shells and 6000 lb. per square inch in the beams.

The front of the hangar will have sliding folding doors operating in three pairs. The roof is insulated with boarding and roofing felt to retain the heat provided by radiant heating panels suspended from the roof and walls.

The scheme was evolved by the contractors, Messrs. John Laing & Son, Ltd., in collaboration with Messrs. Ove Arup & Partners, the consulting engineers. It is estimated that this method of erecting the roof was cheaper due to the saving of scaffolding and plant that results from casting the roof and installing the services and finishes at ground level. Each bay was raised in one week by thirty men.




Fig. 4.—Raising a Column.




Fig. 5.—Method of Transporting and inserting Blocks.




Fig. 6.—Stages of Construction.

A Concrete and Glass Canopy.

A CONCRETE and glass canopy has been constructed at the Savoy Hotel, London, as part of a porte-cochère. It has an area of 2500 sq. ft. and comprises three arched bays; the spans of the side arches are 15 ft. 6 in. with a rise of 1 ft. 9 in. and the span of the central arch is 20 ft. with a rise of 2 ft. 3 in. (Fig. 2). At each end of the canopy a curved reinforced concrete slab, 4½ in. thick, cantilevers upwards.

The arches are supported on inverted tee-beams the bottom flanges of which are curved to accord with the concrete and glass panels. The span of the beams is 32 ft.; they are supported at one end on

bearings cut into the building. The outer supports consist of four circular columns which taper from 15 in. at the top to 12 in. at ground level. The height from the ground to the soffit of the beams is 16 ft. 9 in. The bases of the columns are of reinforced concrete, and are connected by a beam 15 in. square about 6 in. below the ground. All the concrete for the foundations and superstructure was cast in place.

The architects were Messrs. Thurlow, Lucas & Janes, the contractors were Lenscrete, Ltd., and the structure was designed by the British Reinforced Concrete Engineering Co., Ltd.



Fig. 1.




Fig. 2.


Large Water Tower at Dunstable.

A WATER tower with a capacity of 200,000 gallons, and a height of more than 120 ft. is being built at Dunstable for General Motors, Ltd. It will be one of the largest in the country.


The tank is of the Intze type, supported on eight reinforced concrete columns equally spaced on a pitch circle 38 ft. in diameter. The foundations are independent bases resting on chalk, which

occurs 2 ft. below ground level. The underside of the tank will be 100 ft. above the ground and the columns will be braced at intervals of 20 ft. A valve platform consisting of a floor-slab 5 in. thick supported on beams will be provided 7 ft. 6 in. below the underside of the bottom of the tank.

The roof will be a dome with a thickness of 4 in. and a radius of 58 ft., and at



EXTERNAL ELEVATION



SECTIONAL ELEVATION.

the crown there will be a cupola with a diameter of 5 ft. 8 in. and a height of 3 ft. The roof will be connected by a ring-beam to the cylindrical part of the tank, which will have an overall diameter of 47 ft. 6 in., the wall being 16 ft. high and 9 in. thick. A lower ring-beam will connect this wall to the conical part of the bottom of the tank, which will be 12 in. thick and 10 ft. high, and will balance the domed floor. The domed bottom will have a thickness of 12 in. and a radius of 22 ft. 3 in. The main ring-beam will be at the line of intersection of the conical and domed

tank-bottom and will transmit the load to the supporting columns.

A valve-pit below ground between the column bases will contain the valve controls and pipes for the tower. It is 14 ft. 6 in. long, 14 ft. wide, and 8 ft. 6 in. high, and is of reinforced concrete; the walls and roof are 9 in. thick. The floor is 12 in. thick and projects 12 in.

The tower was designed by the British Reinforced Concrete Engineering Co., Ltd., who also supplied the reinforcement, and the contractors are Messrs. Fletcher & Co., Ltd. •

The Construction of Roads on Peat.

TECHNICAL Paper No. 40 of the Department of Scientific and Industrial Research is entitled "A Review of Existing Methods of Road Construction over Peat," and is available from H.M. Stationery Office at 3s. 6d. It has been prepared at the Road Research Laboratory, and gives brief descriptions of methods that have been used in the United Kingdom and elsewhere for the construction of roads over peat. The following notes are given on some concrete roads laid on peat.

Since concrete roads are usually about half the thickness of flexible roads their smaller weight should normally result in less settlement. In addition, concrete roads carrying medium traffic over peat tend to develop less abrupt longitudinal undulations than do flexible pavements. Cracking and severe loss of shape may eventually occur, however, especially if traffic increases.

In Northern Ireland a common practice is to lay doubly-reinforced slabs 8 in. thick directly on the peat or on a base of material taken from old waterbound macadam roads. The slabs are usually about 50 ft. long, 10 ft. or 20 ft. wide, and dowelled at the joints. These roads usually behave reasonably satisfactorily under moderately light traffic. Longitudinal waviness is common, but relatively little cracking occurs. The importance of dowelled joints or of constructing slabs to full width of the road is shown by the fact that differential settlement of adja-

cent slabs usually occurs when dowel bars are omitted. The deformation of some of these roads has, however, become sufficient to warrant total reconstruction, although many still continue to give satisfactory service.

In East Anglia reinforced and unreinforced concrete have been used for minor roads over peat. In general, the performance of these roads has been good. Roads in use up to thirteen years showed that unreinforced slabs 8 in. thick were particularly free from trouble if their length was limited to 12 ft.

In Scotland concrete on main roads with medium traffic over peat has given reasonably satisfactory results. On the Perth-Inverness road an 8-in. doubly reinforced surface was laid, with reinforced beams 18 in. deep under the edge and joints. No noticeable settlement of this road has occurred after 26 years. The concrete road at Spean bridge on the Fort William-Inverness road is doubly reinforced and 8 in. thick, thickened to 15½ in. at the outside edges; the road has settled considerably, although its riding qualities are reasonably good. A concrete road between Newtonmore and Laggan Bridge is doubly reinforced and 8 in. thick; it settled so unevenly that it was covered with a bituminous surfacing. In the only known case in which concrete was used over peat carrying frequent and heavy traffic the road was in frequent need of repair.

Petrol Storage Tanks in London.

FOUR light gasworks feedstock tanks, for the storage of petrol, are now being built for the South Eastern Gas Board at Greenwich, Wandsworth, Croydon, and Sydenham. The capacities of the tanks at Greenwich and Croydon will be 150,000 galls., at Sydenham 100,000 galls., and at Wandsworth 240,000 galls. in two compartments.

In order to reduce the risk of fire, the tanks are below ground and are designed to conform to the requirements of the London County Council; these require the tanks to be of steel surrounded by high-quality concrete, and to be tested

were placed on a steel grillage which rested on a prestressed concrete slab at the bottom of the excavation. A layer of tarred sand, in which drainage channels were formed (*Fig. 1*), was placed on top of the concrete base. The steel side-plates were subjected to the full test load before the surrounding concrete was placed, and were therefore arranged as shown in *Fig. 3* to provide the necessary resistance to bending. The steel plates forming the roof are attached to the underside of prestressed beams, by means of stiffeners cast in place, on an assembly bay adjacent to the tank (*Figs. 4* and *5*), and were then



Fig. 1.—Draining Channels in Base.

with a head of water 1 ft. greater than the depth of the tank. It was also considered desirable that the bottom of the excavation should not be below the level of the ground-water, and the restricted sites available necessitated the use of rectangular tanks. The time of construction was required to be as short as possible.

In the interest of economy all the tanks are of similar construction, the only differences being those due to the capacities required and the configuration of the sites. The following description relates particularly to the tank at Greenwich (*Figs. 2, 3, 5 and 6*); that at Wandsworth is shown in *Figs. 1 and 4*.




The general arrangement is shown in *Fig. 2*. In order to allow the steel lining to be tested for leaks, the bottom plates

moved into position on rollers. The welding was completed, the floor of the tank tested, jacks inserted under each pair of roof beams, and the tank lifted in order to remove the grillage; the structure was then lowered so that the roof beams were supported on previously-prepared side beams and the floor was supported on the prestressed base. The full test load was applied, and the walls concreted.

The sequence of construction is given in the following.

(1) The pit was excavated and the prestressed slab laid at the bottom. Concrete columns supporting the prestressed side beams were then cast along two sides of the pit.

(2) The steel grillage was placed on the base slab, and the floor and walls of the steel tank erected.



SECTION B-B.

Fig. 1.




Fig. 3.—Erecting the Steel Tank.




Fig. 4.—Construction of Roof.



Fig. 5.—Moving Roof Units into Position.

(3) At the same time the precast prestressed roof beams were placed in pairs on the roof plates. Stiffeners were placed between each pair of beams; the reinforcement of the stiffeners passes through holes formed in cleats attached to the plates to ensure that these are firmly connected to the beams.

(4) The roof units were moved along runways consisting of steel sheet piles to the beams alongside the tanks, and then along these beams into position. A special type of roller known as a "mover skate" was used. The longitudinal and peripheral welds in the roof were made, and the steel tank thereby completed.

(5) Jacks were placed under the ends of the roof units, and the tank lifted until

the grillage could be removed. During this operation, temporary suspension rods supported the steel bottom of the tank. The tank was then lowered until the floor rested on the base slab, and the roof beams were supported on the concrete beams at the side (Fig. 6).

(6) The tank was tested, and the surrounding concrete placed and prestressed vertically. Finally the roof was covered with concrete and the ground was back filled.

The work was designed by the Central Construction Department of the South Eastern Gas Board, the general contractor are the Demolition and Construction Co. Ltd., and the steel tank was fabricated by the Redheugh Iron & Steel Co., Ltd.




Fig. 6.—View of Tank after Lowering.

A Swiss System of Prestressing.

APPLICATION TO A BRIDGE IN KENT.

THE bridge described in this article is one of the first structures in Great Britain to be prestressed by the BBRV system of post-tensioning, which was developed some years ago in Switzerland and has since been used elsewhere (the initials BBRV are those of Messrs. Birkenmaier, Brandestini, Rös, and Vogt, the inventors of the system). It differs from other systems in that multiple-wire cables cap-

with a diameter of 0.20 in. or 0.276 in. In order that the enlarged head, called a "button-head" or "nail-head", may be formed properly, the carbon content of the steel should be about 0.7 per cent. The shape and proportions of the head are also important (Fig. 1); tests show that a diameter of about $1\frac{1}{2}$ times the diameter of the wire and a thickness of about seven-eighths of the diameter are




Fig. 1.

able of sustaining working loads exceeding 100 tons are used, and each wire is anchored at each end by means of enlarged heads formed on the wire. Details of a typical cable to provide a force of 90 tons are given in Fig. 1.

The Cables.

A cable may comprise up to 44 wires the number depending on the working load, which for standard cables may be 28, 56, 90, or 125 tons; a cable for a working load of 250 tons is being developed. The space occupied is small in relation to the force in a cable. All wires are cut to the same predetermined length, two steel anchor-heads (each of which is perforated to accommodate all the wires) are threaded over the ends of the wires, enlarged heads are formed at both ends of each wire, and the cable is then ready to be placed in position.

The wire used in this country is generally hard-drawn, with a tensile strength from 100 tons to 110 tons per square inch in accordance with B.S. No. 2691 and

most satisfactory because the strength of the head so formed exceeds the tensile strength of the wire. The head is formed by cold-upsetting of the end of the wire in a machine (Fig. 2) operated by electrical or hydraulic means. The wire is placed in a slot in the machine, the slot is closed to grip the wire, and a crank-operated ram pressing on the end forms the required shape. The process, which occupies only a second or so, is generally carried out near the bench on which the cables are formed; alternatively the heads may be formed on one end of each wire and a portable machine used to form those on the other ends after the cable is placed in position.

It is usual for the cable to be made up completely with a jacking anchor-head at one end and a fixed anchor-head at the other end, the wires being encased in a sheath with enlarged ends as shown in Fig. 1. The complete cable is fixed in the shuttering before concreting. When the concrete has hardened the cables are tensioned and grout is injected in the sheaths.

The anchor-head at the jacking end of the cable is a steel annulus (Fig. 3) perforated with two concentric rings of holes to receive the wires; a larger central hole is tapped to receive a threaded draw-rod. The outer rim of the annulus is threaded to receive a locking ring which transmits the prestressing force to a steel plate bearing against or embedded in the concrete. If the cable is completely made up before insertion in the shuttering, the fixed anchor at the end remote from the jack comprises a square steel block and bearing plate (Fig. 1) without a central hole but perforated to allow the wires to pass through and be retained by the heads.

The sheaths are up to $2\frac{1}{4}$ in. diameter. The enlarged ends are up to 4 in. diameter at the fixed end and $4\frac{1}{2}$ in. diameter at the jacking end. The length of the enlargement at the jacking end is sufficient to allow the anchor-head to lie inside the sheath before tensioning the cable.

Long cables are formed by coupling together two or more cables, on the meeting ends of which jacking anchor-heads are provided, a short threaded rod being screwed into both anchor-heads. It is desirable to tension curved cables and long cables from both ends, and a jacking anchor-head is provided at each end.

An alternative method is to insert the cables in ducts formed in the concrete. The anchor at the fixed end comprises a steel annulus similar to the anchor-head at the jacking end except that it is smaller in diameter because of the absence of the central hole for the draw-rod. A modification of this method is to form the nail-heads on one end of the wires, insert the wires in an anchor-head of the smaller



Fig. 2.—Machine for Forming Heads on Wires.

type described, insert the wires and anchor-head into the duct from the fixed-end, thread a jacking anchor-head over the free ends of the wires, and finally form the nail-heads on these ends.

The ducts in which the cables are inserted are formed by one of the usual methods. The diameter of the duct is between $1\frac{1}{2}$ in. and $2\frac{1}{2}$ in., depending on the number of wires in the cable. The duct is enlarged at the fixed end to between $2\frac{1}{2}$ in. and $4\frac{1}{2}$ in., to allow for the spreading of the wires as they enter the anchor-head, and to between $2\frac{1}{2}$ in. and $5\frac{1}{2}$ in. at the jacking end to allow the anchor-head to be a short distance inside the duct before the cable is tensioned. If completed cables are inserted the ducts must be large enough throughout to allow for the passage of the annular fixed-end anchor-heads. If the nail-heads are formed on one end of the wire after it is inserted in ducts, the length of the enlarged duct at the fixed end is increased so that the fixed-end anchor can enter the duct sufficiently far to enable the nail-heads to be formed at the other end.




Fig. 3.—Anchor-head at Jacking End.

Tensioning the Cables.

The cables are tensioned by an hydraulic jack with a capacity of 100 or 150 tons. The jack is operated manually by a lever on the body (Fig. 4), and can also be adapted for operation from a distance by a high-pressure pump operated manually or electrically. A threaded draw-rod is screwed into the central hole in the anchor-head. The jack has a hole centrally through the body so that it can be slipped over the draw-rod in which position it is retained by a lock-nut on the protruding

end of the draw-rod. A steel barrel acts as a spacer between the jack and the bearing-plate.

The jack pulls the draw-rod, bringing the anchor-head with it and thereby tensioning the wires. When the required force or extension is obtained, the locking-ring is screwed tightly against the bearing-plate; the final tightening is by means of a hammer and a bar, the end of the bar engaging in slots in the periphery of the locking-ring. The anchorage of the wires can be inspected at any time during the operation and a broken wire can be detected before grouting.

The extension is indicated by graduations on the ram of the jack. The force is indicated by the manometer attached to the jack or more accurately (within ± 1 per cent.) by means of a dynamometer (Fig. 5). The losses due to friction, shrinkage, and creep can be allowed for by attaching the dynamometer and oper-

ating the jack at any time after the initial tensioning so long as the ducts have not been grouted. It is usual for these losses to be made good immediately before grouting, by re-tensioning the cable to the initial force assumed in the design. There is no loss due to slipping of the wires at the anchorage.

Application to a Service Bridge.

The bridge shown in Fig. 6 and illustrated in course of construction in Fig. 7




Fig. 4.—Draw-rod and Jack.

December, 1958.



Fig. 5.—Jack with Dynamometer.

supports services at the works of the South Eastern Gas Board at Isle of Grain, Kent, and comprises two spans of about 95 ft. and one of about 34 ft. Each span comprises two prestressed longitudinal main girders of I-section supporting precast transverse beams carrying precast deck slabs. The ends of the transverse beams rest on the bottom flanges of the main girders and are secured by two tensioned 0.276-in. wires anchored in the girders. The girders are supported on prestressed double-cantilever cross-heads carried on reinforced concrete frames as shown in *Figs. 6 and 7*. One end of each main girder is fixed and the other carried on a roller bearing in the longer spans, or a sliding bearing in the shorter span. The main girders are made with precast blocks (*Fig. 8*) which were assembled in position on the temporary steel Bailey bridge shown in *Fig. 7*. The meeting faces of the blocks were bush-hammered and after erection and alignment the joints were filled with mortar comprising 1 part (by volume) of cement to 2 parts of sand; the water content was about 6 gall. per 112 lb. of cement. The cables were not tensioned until the grout attained a compressive strength of more than 2000 lb. per square inch.

Each of the longer girders has five

cables, two of which have a nominal capacity of 50 tons and three of 100 tons. The nail-heading at the jacking ends was done after the cables had been inserted in the ducts; the enlarged part of the duct at the fixed end was therefore longer than usual, so that the anchor-head could pass inside the duct to enable the wires at the jacking end to be pulled sufficiently far out of the duct to enable the heads to be formed on the ends. The three cables in the bottom flange are contained in an elliptical duct, thereby avoiding the reduction of the area of concrete which would occur if three large circular ducts were provided. The profiles of the cables are shown in *Fig. 9* and the positions at the end of the girder in *Fig. 4*.

The cables were tensioned with the jack operating at the central support and in the following sequence: No. 1 (lower curved 50-tons cable); No. 2 (upper curved 50-tons cable); No. 3 (outer straight 100-tons cable); No. 4 (inner straight 100-tons cable); and No. 5 (central 100-tons cable). At the stage shown in *Fig. 4*, cables Nos. 1 and 2 have been tensioned, locked, and grouted; cable No. 3 has been tensioned and locked, but the draw-rod is still in position; cable No. 4 is being tensioned, the jack being in position; cable No. 5 has not




Fig. 6.—Prestressed cre

December, 1958.





Fig. 7.—Prestressed Concrete Service Bridge :
two Spans during Construction.

yet been tensioned, and the anchor-head is visible just inside the enlarged part of the duct.

Each 50-tons cable contains twenty-six wires, and each 100-tons cable forty-two wires, all of 0.2 in. diameter. The average tensile strength of the wires is 112 tons

per square inch and the 1 per cent. proof stress not less than 98.8 tons per square inch. The initial tensile stress in the wires was about 170,000 lb. per square inch (about 5300 lb. per wire) in each straight cable and an effective force of about 5000 lb. per wire in the curved



Prestressed Concrete Girder Bridge.

cables. Before grouting, the cables were re-tensioned to about 5000 lb. per wire to make good the losses ; the grout was similar to the liquid mortar between the blocks, but it also contained a chemical to retard setting and a non-shrinking agent. The South Eastern Gas Board is contemplating the use of a bituminous liquid such as gas-works tar, instead of a cementitious grout, for injection into ducts to ensure greater protection of the wires.

After the tensioning and grouting operations were completed, the anchor-heads were embedded in concrete in the recesses at the ends of the girders and held in place by small grids of mild steel bars (Fig. 10) welded to the bearing plates.




Fig. 8.—Precast Block with Bush-Hammered Face, showing Cable Ducts.

Stresses during Prestressing.

The sequence of tensioning the cables is important to ensure that no significant tensile stresses are produced. The stresses are not easy to determine because of the variable contribution of the dead load ; the weight of the precast blocks forming the girder caused the temporary steel bridge to deflect, and when the first cables were tensioned the weight on the middle of the steel bridge was reduced. Consequently the elastic deflection of the steel bridge was reduced so that it still supported some of the weight of the blocks, even at the middle of the span. All the weight was transferred entirely to the end supports of the girder only when the last cable was tensioned.

As tensioning of the cables proceeded observations were made of the degree of freedom of the blocks forming girder No. 2. It was found (Fig. 10) that all the blocks were supported on the steel bridge when cables Nos. 1 and 2 were tensioned ; a few central blocks were free when cable No. 3 was tensioned ; and all but a few blocks at each end were free when cable No. 4 was tensioned. The diagrams on Fig. 11 show the probable stresses at an end joint and at a joint near the middle of the span during the tensioning operations. Comparison with the corresponding diagrams, assuming all blocks to be free of the steel bridge, show that in some cases the stresses are likely to be the reverse of what might be expected.

Reduction of Prestress due to Friction.

Some observations were made to determine the loss due to friction between the curved cables and the sides of the ducts. In particular the loss in the upper cables in three of the double-cantilevered cross-heads at the supports (Fig. 9) was investigated. The radius of these cables is about 26 ft. and the length about 30 ft. ; the ducts comprise corrugated steel tubes of $1\frac{1}{2}$ in. internal diameter. The two lower cables (Nos. 2 and 3) turn through an angle of about 55 deg. and the upper cable (No. 1) through about 47 deg. Each cable was tensioned with a force P_0 of about 58 tons with the jack and dynamometer attached at one end. The locking-ring at this end was then tightened, and the jack released and transferred with the dynamometer to the other




Fig. 9.—Profiles of Prestressing Cables.

TABLE I.

Cross head	Radius (ft.)	Angle α		Forces		Reduction due to friction			
				Jacking force (tons) P_0	Dynamometer reading (tons) P_D	Measured		Calculated	
		deg.	radians	(tons) P_0	(tons) P_D	(tons) $P_0 - P_D$	(per cent.) $\frac{P_0 - P_D}{P_0} \times 100$	(tons) $P_0 - P_D$	(per cent.) $\frac{P_0 - P_D}{P_0} \times 100$
A	25.85	47	0.820	58	45.8	12.2	21.0	12.7	21.8
B	25.85	47	0.820	58	46.6	11.4	19.5	12.7	21.8
C	25.85	47	0.820	57.7	44.9	12.8	22.2	12.7	21.8

end. A pull was applied to the anchor-head at this end, and at the instant when the locking-ring at this end became free the force P_D at this end was recorded. The difference between P_0 and P_D represents the reduction due to friction of the cable in the duct and the friction of the jack. Before removing the jack, this reduction was made good by tensioning the cable from this end to the full design load.

The observations are given in *Table I*, which also shows the theoretical reduction calculated in accordance with the exponential formula given in the British draft code for Prestressed Concrete and the draft Code for Liquid-retaining Structures. The formula can be expressed in a modified form, namely, that the reduction in tons due to friction at a distance of x ft. from the tangent point nearer the

jacking end is $\left[1 - e^{-\frac{\mu x}{R}} \right] P_0$ tons, in




Fig. 10.—The Anchors.




Fig. 11.—Effect of Tensioning Cables.

which P_0 is the jacking force in tons, R the radius of the cable (or inner edge of the duct) in feet, and μ the coefficient of friction which in this case is assumed to be 0.30 for steel wires in a corrugated-steel duct. For the total reduction $P_0 - P_D$ in the entire length of cable between the tangent points, x is the length of the curved part of the cable and therefore the term $\frac{x}{R}$ is equal to α radians, in which α is the angle through which the cable is deflected in the length x ft. Therefore

$$P_0 - P_D = \left[1 - \frac{1}{e^{\mu x}} \right] P_0 \text{ tons.}$$

Table I shows that the measured total reduction was between 20 per cent. and 22 per cent., whereas the reduction calculated at the time of the design of the

structure was between 21 per cent. and 22 per cent. excluding the friction of the jack but assuming $\mu = 0.3$. If a coefficient of friction of 0.35 is assumed, the calculated reduction is between 25 per cent. and 26 per cent. The test shows that the assumption of a coefficient of 0.3 is reasonable and gives slightly conservative results. The diagrams in Figs. 9 and 11 and the data in Table I are based on similar diagrams presented by Mr. Chas. E. Reynolds at the International Congress on Prestressed Concrete held in Berlin in May, 1958.

The bridge described in the foregoing was designed by the South Eastern Gas Board in collaboration with Messrs. Simon-Carves Ltd., who are the licensees in Great Britain for the BBRV system. The contractors were Sir Robert McAlpine & Sons, Ltd.

Exhibition of Precast Concrete.


An exhibition of more than 200 photographs of various types of precast concrete products was held in London in November under the auspices of the Cement & Concrete Association, and is now visiting other cities. The exhibition may be seen at the following places. Admission is free.

- December 15 and 16. Houldsworth Hall, Manchester.
- December 18 and 19. Bluecoat Chambers, Liverpool.
- January 5 and 6. McLellan Galleries, Glasgow.
- January 8 and 9. Freemason's Hall, Edinburgh.
- January 12 and 13. Marryat Hall, Dundee.
- January 19 and 20. Central Hall, Gosforth, Newcastle.
- January 22 and 23. Corn Exchange, Leeds.
- January 26 and 27. Mappin Hall, Sheffield.
- January 29 and 30. Technical College, Nottingham.
- February 2 and 3. Stuart & Suckling Halls, Norwich.

December, 1958.

New Anchor for Prestressing Bars.


The wedge anchor-grip shown in the illustration has been developed for use with the Lee-McCall prestressing system; the wedge can be anchored anywhere on the bar, whereas a threaded end can be



used only on bars of predetermined lengths. The use of this grip enables bars of stock lengths to be used, and the end of the prestressed member is nearly flush. The recommended initial jacking stress for Macalloy bars anchored with wedge grips is 45 tons per square inch. Threaded anchors are still available.

Fibrous Material for Column Shutters.

THE illustration shows the use of a tube of fibrous material as shuttering in the construction of sixty-five reinforced concrete columns at a building at Bournemouth. When the reinforcement is fixed the tubes are lowered over it and fixed at the top and bottom and the concrete placed. Three days later a hose is used to soak the tubes with water and they are cut away. It is claimed that the cost is about two-thirds of the cost of other shutters for round columns. The architect is Mr. Alan A. Briggs and the contractors Messrs. W. E. Chivers & Sons, Ltd. The tubes were supplied by Venesta, Ltd.



440

Accidents during Prestressing.

THE "Annual Report of the Chief Inspector of Factories for the Year 1957" (H.M.S.O. Price 5s.) states that serious accidents, some fatal, have occurred when high-tensile steel has broken or has been suddenly released during tensioning in the production of prestressed concrete. If it breaks the steel whips out of the mould or concrete at a dangerous speed, and to eliminate this risk it is recommended that tunnel-shaped guards made of expanded metal or stout wire mesh should be used.

If the tensioned reinforcement is suddenly released, for example by failure of the anchoring device, it may fly out with sufficient force to impale anyone nearby. To overcome this risk, it is recommended that strongly-constructed shields of steel or timber be fitted behind each anchorage, that the jacks should be operated from the side of the beam, and that access to the area behind the anchorage should be prohibited until the tensioning operation is completed.

Strength in Bonding of Indented Prestressing Wires.

INVESTIGATIONS on the effects of repeated loading of prestressed beams showed that, when the concrete is of high strength, deformed wires offer little advantage over slightly-rusted plain wires in developing bond with the concrete and in controlling cracking. The ultimate strength of beams with post-tensioned and grouted cables, in which failure was due primarily to crushing of the concrete, may be calculated by simple methods provided that the initial tension in the cables conforms with normal practice. Associated tests on prestressing wires have confirmed that the loss of prestress resulting from relaxation of stress in the steel is likely to be between 4 and 5 tons per square inch in the case of wire from coils of large diameter, and that special treatment in manufacture can provide a wire that results in a loss of only about 1 ton per square inch. [From "Building Research, 1957." H.M. Stationery Office. Price 5s. 6d.]

THE CONCRETE SERIES

For detailed prospectuses of books on concrete, priced in sterling and dollars, send a postcard to

CONCRETE PUBLICATIONS LTD.
20 Dartmouth Street, London, S.W.1

December, 1958.

Additional British Standard Loadings.

AN amendment to British Standard Code No. 3, "Code of Functional Requirement of Buildings, Chapter V—Loading", issued recently contains the following additions and alterations.

WIND PRESSURE.—The recommendations relating to wind pressure in the 1952 edition of the Code have been extended to include chimney shafts, sheeted towers, and structures that are permanently without walls, such as braced towers, gantries, and girders. The basic wind pressure on such structures is determined by the height of the structure and the greatest probable velocity of the wind at a height of 40 ft. The basic intensities of pressure p' apply to structures of which the members have non-circular cross sections, and are given in the accompanying table. In the case of structures less than 200 ft. in height the pressures exceed those recommended for ordinary buildings of equivalent exposure; the difference is about

50 per cent. for very low structures, about 20 per cent. for structures 50 ft. high, and 10 per cent. to 15 per cent. for structures 100 ft. high. The data apply to steady wind pressures, and warning is given that certain structures, including reinforced concrete chimneys, may oscillate when subjected to the effects of the wind. Whereas the basic intensity of pressure on a building is assumed to act uniformly on the entire height, the basic pressure on a chimney or tower is assumed to vary from a maximum at the top to a minimum at the bottom; the intensity at any plane at any height depends on the height of the plane above the ground.

For structures which consist of members of circular cross section, the recommended design pressure is $0.7p'$, but for single members of circular cross section the pressure is $0.6p'$. In the case of isolated structures such as chimney shafts and sheeted towers the recommended design

WIND PRESSURE (p') ON UNCLAD STRUCTURES, SHEETED TOWERS AND CHIMNEYS

Height of the part of the structure in feet above ground level	Wind pressure (p') at any point on a structure in lb/sq. ft when the velocity in miles per hour at 40 ft above the ground is						
	50	55	60	65	70	75	80
up to 10	7	9	10	12	14	16	18
20	8	10	12	14	16	18	21
30	9	11	13	16	18	21	24
40	10	12	14	17	20	23	26
50	11	13	15	18	21	24	27
60	11	13	16	19	22	25	28
70	12	14	17	20	23	26	30
80	12	15	17	21	24	27	31
100	16	16	18	22	25	29	33
120			19	22	26	30	34
140			20	24	27	32	36
160			21	24	28	33	37
180			21	25	29	33	38
200			22	26	30	34	39
250				27	32	36	41
300				28	33	38	43
350				30	35	40	45
400				36	36	41	47
450				37	37	42	48
500 or more				38	38	43	49

(1) Structures more than 100 ft. in height should be designed for velocities not less than those to the right of the stepped line. (2) The maximum value of the mean velocity (at an effective height of 40 ft.) during a period of one minute should be used in design.

pressure is p' multiplied by the shape factor given in the Code plus 10 per cent. ; that is when the ratio of height to width at the base of a shaft or tower is not less than eight the design pressure is $0.77p'$ if of circular cross section, $1.1p'$ if octagonal, $1.43p'$ if of square cross section and the direction of the wind is normal to one face, or $1.1p'$ if of square cross section and the direction of the wind is normal to a diagonal.

The smaller reduction due to shape and the greater basic pressure lead to a significant increase in design pressures compared with those for ordinary buildings. Consider, for example, a circular chimney of 5 ft. diameter, projecting 40 ft. above the roof of a building 40 ft. high, and subjected to a wind with a velocity of 72 miles per hour. Treated as a projection above the roof, the design pressure is $0.7 \times 22 = 14.4$ lb. per square foot ; considered as a chimney shaft under the additional recommendations, the design pressures are $0.77 \times 25.2 = 19.4$ lb. per square foot at the top and 16.3 lb. per square foot at roof level. The total pressure on the chimney, considered as a projection above the roof, is $5 \times 40 \times 14.4 = 2880$ lb. ; considered as a chimney shaft it is $(19.4 + 16.3) \times 0.5 \times 5 \times 40 = 3570$ lb. In the first case the centre of pressure is 20 ft. above the roof and the bending moment at roof level is 57,600 ft.-lb. ; in the latter case the centre of pressure is about 25 ft. above the roof and the bending moment is 73,230 ft.-lb.


Recommendations are given permitting the reduction of pressure on the leeward members of framed or lattice structures if they are partially shielded by the windward members. The notes on the permeability of buildings under the influence of wind have been elaborated.

GARAGE FLOORS.—New loadings are given for garage floors for vehicles not exceeding 2½ tons in weight. As the loading given in the Code of 1952 (comprising a minimum imposed load of 80 lb. per square foot or an alternative minimum uniformly-distributed total load of 640 lb. per foot of width in the case of slabs and 5120 lb. per square foot in the case of beams) is not specifically superseded, it may be assumed that such floors should be designed for whichever loading gives the greatest bending moment or shearing force.

The new loadings for vehicles not ex-

ceeding 2½ tons in weight are : (a) for floors used only for parking, the design load due to the most adverse arrangement of the vehicles, taking into account the actual wheel loads. (b) For floors used as garages other than for parking only, as (a) but not less than 80 lb. per square foot of floor for slabs and 50 lb. per square foot of floor for beams. This may be slightly less severe than the loading in (a), but it should be remembered that a floor normally used for garage services may sometimes be used for parking vehicles closely together, and it seems advisable to design all floors associated with the garaging or parking of light vehicles for the loading given in the Code or for the most adverse arrangement of vehicles.

BALCONIES AND STAIRS.—It is recommended that balconies be designed for the same loading as the floor or other area to which they give access. Although the recommendation in the 1952 Code that the minimum alternative loadings do not apply to cantilevered beams and slabs has not been specifically cancelled, the revisions imply that it is, in part at least, superseded in view of the new recommendation that the span of a cantilevered balcony shall be considered to be the projection of the cantilever when considering the alternative load. Cantilevered steps that are structurally independent should be designed to resist an alternative load of 300 lb. acting at the free end.



Trent Gravels 10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{4}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD
ATTENBOROUGH
Telephone Beeston 54255

NOTTS
December, 1958.

A Dome at Dallas, Texas, U.S.A.

In this journal for January, 1956, Mr. Charles S. Whitney described the design of a dome of 300 ft. diameter for the Dallas Memorial Auditorium (Fig. 1). The building has recently been completed,

and the method of construction is shown in Fig. 2.

The dome was cast in segments, the same shuttering being used for each. A central tower, about 90 ft. high, was first




Fig. 1.




Fig. 2.—Shuttering for Opposing Sections of the Dome.

LINCOLN
NEWARK
GRANTHAM
MELTON
MOWBRAY

els
week

$\frac{1}{4}$ in.
concrete
Prompt
ive prices
es.

LTD
NOTTS

erected, on which the central part of the dome was cast. Radial bars were left projecting from this part to form a connection with the segments. The shuttering for the segments was then erected, together with a supporting steel framework mounted on rollers; each section of shuttering was supported at four intermediate points and at each end. The

segments were concreted, the unbalanced thrust being resisted by the central tower until the concrete had hardened; the shuttering was then released and moved into the position to support the adjacent segments.

The architect is Mr. George L. Dahl, and the consulting engineers are Messrs. Amman & Whitney.

FIFTY YEARS AGO.

FROM " CONCRETE AND CONSTRUCTIONAL ENGINEERING ",
NOVEMBER-DECEMBER, 1908.*



THE illustration shows a three-story reinforced concrete transit shed, designed on the Hennebique system, in course of construction at Sandon Dock, Liverpool, in 1908. It is 628 ft. long, 78 ft. wide, and 56 ft. high, and was designed for imposed loads of 20 cwt. per square yard on the first floor, 14 cwt. on the second floor, and 3 tons on the ground floor. Electrically-operated travelling cranes of 1½ tons capacity, with an outreach of 46 ft. from the face of the shed, were later erected on the roof. The columns are at centres of 26 ft. longitudinally and 30 ft. 10 in. and 47 ft. 2 in. transversely. On the landward side the upper floors cantilever 16 ft. beyond the ground floor. The consulting engineers were Messrs. L. G. Mouchel & Partners.

The Mersey Docks and Harbour Board inform us that, as a result of the suspension of the usual maintenance work during the war of 1939-1945, it became necessary to repair the structure; the concrete cover had spalled, exposing the reinforcement over considerable areas, and the external faces were covered with reinforced gunite 2 in. thick. The cast-iron window sashes were badly corroded, and were replaced with precast concrete sashes.

* "Concrete and Constructional Engineering" appeared in alternate months until September, 1909.

New Type of Long-span Roof.

A METHOD of constructing roofs with long spans, which was developed in South America about seven years ago and has now been introduced into this country, is known as the "Silberkuhl" system, and has been used on about seventy structures in South America and Europe.

External and internal views of such a roof are shown in *Figs. 1 and 2*. It consists of conoidal slabs, which may be cast in place or precast, and tied arches of structural steel. The upper and lower booms of the arches support adjacent slabs, and are connected vertically by a lattice. The space between the booms is glazed to form a north-light. The slabs and the arches are connected structurally.

It is stated that the system is economical for clear spans of between 70 ft. and

210 ft., and that loads of up to 15 tons can be suspended from any point; other advantages claimed for the system are good and uniform natural lighting and insulation.

The roof shown in *Figs. 1 and 2* has a span of 100 ft. and the arches are at centres of 23 ft. It supports two suspended cranes, each of 3 tons capacity, on longitudinal girders connected to the lower booms of the arches. We are informed that more than 500,000 square feet of this type of roof are now being built in Great Britain.

For spans of up to 70 ft., precast prestressed slabs are used. The units are hyperbolic (*Figs. 3 and 4*), with a thickness of 2 in. and a width of up to 8 ft. A hyperbolic surface can be generated by




Fig. 1.—Roof of 100 ft. Span.



Fig. 2.—Interior of Building shown in Fig. 1.




Fig. 3.—Prestressed Roof Slabs.




Fig. 4.—Method of Casting Slabs shown in Fig. 3.




Fig. 5.—Roof shown in Figs. 3 and 4.

A general view of Associated British Malsters' new malting plant at Knapton




WILLIAM
THORNTON
AND SONS LIMITED

**General Contractors for
NEW MALTINGS & SILO AT KNAPTON**

Specialists in Reinforced Concrete Silos
for Grain and Fodder. Any capacity

38 WELLINGTON ROAD
LIVERPOOL

LARK Lane 1921 (4 lines). Grams: "Thornpool"



POWER BAR CUTTERS

The BRRL.5A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable by reason of its compact arrangement, and is powered by an electric motor and self-tensioning Vee-belt drive. The cutting blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Let us send you full details.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580 Telegrams: Cambelgi, Chatham.

TIMBER SHUTTERS & MOULDS

delivered
to the site
ready for use

with or
without
**PLASTIC
LININGS**

This is one of the many excellent examples of timber shutters with a plastic lining which we have supplied complete and ready for use on the site to contractors engaged in concrete work. The shutter illustrated was used by Messrs. Holland & Hannen and Cubitts (Great Britain) Ltd. for the construction of eight columns (each 14 ft. high and 4 ft. 6 in. in diameter) for a bridge on the St. Albans By-Pass. The plastic lining remained in perfect condition for each of the eight columns, and pro-

duced a superior surface finish for each casting. The first-class service we offer to the concrete industry has proved over and over again that by sub-letting your shuttering work to us you effect every possible saving in time, labour and money.


28 cu.

ut only.

seating

thus red

the mad



In addition to supplying timber shutters, we also offer an exacting service in the supply of ready-to-use moulds to any design and size for precast structural members and other concrete units. However intricate the mould, we are fully equipped to cater for all requirements. Economical prices and early delivery are assured for contracts in any part of the country.

MAY & BUTCHER LTD


HEYBRIDGE BASIN, MALDON, ESSEX. TELEPHONE: MALDON 698

★ prestressing equipment for FREYSSINET AND P.S.C. MonoWire SYSTEM

THE P.S.C. MONOWIRE
POST-TENSIONING
SYSTEM
STRESSING A
12/276 CABLE
ON A P.S.C. 12-WIRE
ANCHORAGE

•

WIRES ARE TENSIONED
AND ANCHORED
INDIVIDUALLY



PSC




EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDDLESEX
Telephone: Uxbridge 5242

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

NEW OFFICES
FOR THE
NORTH THAMES GAS
BOARD



ARCHITECT: ELIE MAYORCAS F.R.I.B.A., A.A.DIP. (HONS.)

PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361

The **NEW** 
COMPRESSION TESTING
MACHINE

it's PORTABLE!



for tests on
 concrete cubes
 cylinders etc.

★ Ideally suitable for use on construction sites.

★ Easily portable—weighing only 3½ cwt.

★ Compact—less than 3 feet high.

★ Capacity 150 tons by increments of ¼ ton.

★ Convenient controls including load pacer.

This latest development in our range of Compression Testing Machines incorporates a unique and patented method of load measurement. Two gauges indicate the load exerted on the specimen by measuring the magnified elastic deformation of the frame of the machine. An integral load-pacing device enabling tests to be performed at constant rates in accordance with British Standards makes it the completely ideal portable Compression Tester.



We shall be pleased to supply further details on request.

SAM'L. DENISON & SON LTD.

HUNSLET FOUNDRY · MOOR ROAD · LEEDS 10
 Tel: Leeds 7-5488 Grams: Weigh Leeds 10'


Area Offices at

LONDON
 SLOane 4628

BIRMINGHAM
 Midland 3931

MANCHESTER
 Blackfriars 1986

LEEDS
 Leeds 2-8433



The cable bridge built for the South Eastern Gas Board at the Isle of Grain, Kent.

BBRV system of prestressed concrete

THE FIRST BRITISH APPLICATION

This cable bridge is the first application in Great Britain of the BBRV post-tensioning system for prestressed concrete, a system widely used in Switzerland, Austria and Western Germany. Simon-Carves Ltd. are the sole licensees in Great Britain and Northern Ireland. The positive nature and proved safety of the anchorages and cables allow large forces to be used. A comprehensive range of standard cable sizes catering for forces up to 220 tons is available.

BBRV POST-TENSIONED PRESTRESSED CONCRETE BY

Simon-Carves Ltd

STOCKPORT, ENGLAND



AUSTRALIAN REPRESENTATIVES: Simon-Carves (Australia) Pty. Ltd., 25-31 Wilson Street, Botany, N.S.W.
SC204

Steel Reinforcement

A complete service of Design, Fabrication and Fixing of Steel Reinforcement for all types of Reinforced Concrete Construction.



M.S. Bars to B.S.S. 785, bent, bundled and labelled, delivered to site ready for fixing. No loss of time in checking and sorting material. No loss of material due to prolonged storage on site.

T. G. JONES
AND COMPANY LIMITED



REINFORCEMENT ENGINEERS

17 BUCKINGHAM PALACE GARDENS
LONDON, S.W.1 Tel: SLOane 5271

Head Office: Wood Lane, London, W.12
Tel: Shepherds Bush 2020
South Wales Office: Bute Street, Cardiff
Tel: 28786
Works: Shepherds Bush, London, Neasden, Mid
Tregarth, Glam.

— REINFORCED CONCRETE, CIVIL ENGINEERING AND BUILDING CONTRACTORS —

monk**road sense A1**

Straight to the point . . . Monk construction thrusts ahead in this 2½ mile section of the new Great North Road, between Brampton Hut and Buckden. With a clean sweep, the dual carriageway eliminates tortuous bends . . . saving time and lives. At Brampton Hut, a roundabout replaces the 'killer' crossroads at the junction of the Huntingdon/Thrapston road. Monk 'know-how' and equipment keep the contract ahead of schedule.

County Surveyor:

T. H. Langstaff, O.B.E., M.I.C.E., F.R.I.B.A., M.T.P.I.,
Huntingdonshire County Council**monk****Warrington and London****A. MONK & COMPANY LTD**

Offices at: Stamford, Hull & Middlesbrough




REINFORCEMENT BY MCCALLS

**A NEW APPROACH TO
REINFORCEMENT IN CONCRETE ROADS**


MATOBAR ROAD MESH

**concentrates the steel
where it is needed**



'MATOBAR' Concentrated Edge Reinforcement for concrete roads puts the steel where it is needed, that is along the edges and at the corners. Here it acts as an extra bonding medium, resisting any tendency to crack.

A typical 'Matobar' Road Mesh, corresponding to BS104 and costing no more, has a sectional area of steel per foot width of 0.435 sq. in. at the edges and 0.217 sq. in. at the centre of the slab, compared with standard mesh giving 0.330 sq. in. all across the slab. Write for the 'Matobar' Road Mesh Leaflet, which gives full particulars and the most effective methods of utilization.



McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 0428

PORTSMOUTH: COSHAM 78702

BIRMINGHAM: ACOCKS GREEN 0229

NEWCASTLE: 38793

PRESTRESSING
STEEL
by MCCALLS
The
LEE-McCALL SYSTEM

McCALL & COMPANY (SHEFFIELD) LIMITED

MCCALLS MACALLOY LIMITED

PRECISION ROOFS LIMITED

MCCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

MCCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

MCCALLS MACALLOY (CANADA) LIMITED

SRB 24

ADS

SH

RATED
STARTcrete
and
sting

'Visqueen' being laid under the runway of the Gatwick Development Project. Consulting Engineers: Frederick S. Snow and Partners; Contractors: Sir Alfred McAlpine & Sons Limited.

Under the runway and roads at Gatwick Airport there's **VISQUEEN** polythene sheeting— almost $\frac{3}{4}$ - million square yards of it!

'V_ISQUEEN' was the polythene sheeting used under the runway and roads at Gatwick Airport as a separation and slip membrane. As a result stress cracking was virtually eliminated in the top slab because it was not keyed to the base. The paving concrete was able to move more freely both during the curing period and subsequently with temperature changes. Furthermore, the 'Visqueen' membrane prevented the fats and moisture draining out of the concrete during curing.

'Visqueen' polythene sheeting is also resistant to acids and alkalis. For this reason it

will protect concrete slabs from attack by acidic sub-soil.

The light weight of 'Visqueen' makes it very easy to handle and it is available in very wide widths to ensure maximum efficiency and reduce wastage in overlaps. Indeed, at Gatwick Airport, specially made widths of 15 feet were used. 'Visqueen' is also efficient as a water and water vapour barrier.

Write to the address below for literature describing more fully the uses of 'Visqueen' polythene sheeting in the building industry and for the name and address of your nearest stockist.

VISQUEEN

the builder's polythene sheeting

BRITISH VISQUEEN LIMITED · STEVENAGE · HERTS · 'PHONE: STEVENAGE 1310

A subsidiary company of Imperial Chemical Industries Limited

BV.112



For over 60 years

this trade mark has stood for speed and strength in reinforced concrete work.

DRAGON

(Brand)

PORLAND CEMENT

Supplied by

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.
PENARTH, SOUTH WALES

Telephone : 57301-4

Telegrams : "Cement, Penarth"

12, 16, 18 STOREYS



High buildings go up fast the Wates way



12-storey blocks at Roehampton, 16-storey cluster block at Bethnal Green, the huge 18-storey blocks at Brandon Estate, Southwark . . . these are just a few of the Wates achievements in the field of high building.

Enthusiastic co-operation between developer, architect, engineer and contractor at every stage from pre-planning to completion, brings the same result whether applied to multi-storey projects or any other class of building. Wates build on time and within the budget.

Left: 16-storey cluster block, Bethnal Green.
Architects: Fry, Drew, Drake and Lasdun.



Above: 12-storey point blocks for the L.C.C. at Roehampton.
Left: 18-storey flats for the L.C.C. at Brandon Estate, Southwark.
Chief Architect: Hubert Bennett, F.R.I.B.A.
Principal Housing Architect: H.J. Whitfield Lewis, F.R.I.B.A.

Ideas become concrete when


WATES BUILD

WATES LTD Building & Civil Engineering Contractors

HEAD OFFICES: 1258-1260 LONDON ROAD, S.W.16. Telephone: POLLards 5000
LONDON • BIRMINGHAM • DUBLIN • NEW YORK




PLYWOOD SHUTTERING



Photographs by courtesy of the British Broadcasting Corporation

For the new B.B.C. Television Centre at Wood Lane London



Once again $\frac{1}{4}$ " Thamesply standard concrete shuttering plywood, (W.B.P.* Phenol bonded to B.S. 1203) was selected by **HIGGS and HILL LTD.** The finest plywood available for shuttering, it is rigid, durable, economical and gives a fine finish.

* Weather and boil proof to B.S. 1203



CONCRETE SHUTTERING

(Phenol Bonded W.B.P. Test)

Supplied only through the usual trade channels

THAMES PLYWOOD MANUFACTURERS LTD, Harts Lane, Barking, Essex.

Telephone: Rippleway 5511


CEMENTATION PUTS NEW LIFE INTO NEWHAVEN BREAKWATER



The artist's illustration of Newhaven harbour has been based on an old print which was made in 1878 to record the construction of the breakwater.

Storms and heavy seas, pounding the structure throughout the years, have seriously reduced its stability. Cementation has come to the rescue and given the breakwater a new lease of life by its proved and tested methods of consolidating masonry and concrete structures.

The Cementation Co. Ltd. has the experience, the facilities and the resources to carry out this type of work in any part of the world.




The **CEMENTATION**
COMPANY LIMITED

London Office : 20 Albert Embankment, S.E.11.

Works & Offices :
BENTLEY WORKS
DONCASTER
Tel. : Don. 54177-8-9

Tel. : RELiance 7654



FOR
REINFORCING
ROUNDS
OF EVERY
DESCRIPTION

We can supply from stock a complete range of Deformed Reinforcing Rounds in diameters from $\frac{3}{8}$ " to $1\frac{1}{2}$ " produced to A.S.T.M. Specification A 305-56T (deformations)





George Gadd & Co. Ltd

STEEL RE-ROLLERS

CHURCH LANE, TIPTON, STAFFS

Telephone: Tipton 1802-3





Concrete

STRUCTURES



Portion of new Central
Laboratory for Richard Thomas
& Baldwin Ltd., Scunthorpe,
showing "Mushroom" column
at apex.


Architectural design by
Clark, Hall & Scorer (Lincoln).
Structural design and erection by
Concrete Services Ltd.

Main Contractors:
F. Shepherd & Son Ltd., Hull

Concrete Services Ltd

OUSE ACRES BOROUGHBRIDGE RD YORK PHONE 78475

Lillington's No. 1 METALLIC LIQUID



FOR THE PLASTICS INDUSTRY

Contractors :
Messrs. J. Gerrard & Sons Ltd.

In the last 10 years over £2,500,000 has been spent by Messrs. BX Plastics Ltd. on machinery and equipment for the manipulation of plastics, and Brantham has become one of the largest factories of its kind in the world.

It is a tribute to Lillington's that for this important project their No. 1 Metallic Liquid was selected for use in the concrete floors to make them hard, dustless and waterproof and capable of withstanding exceptionally heavy wear and tear.

No. 1 Metallic Liquid has been used very extensively for waterproofing concrete floors, retaining walls, foundations and renderings for over 40 years and continues to be used in ever increasing quantities because it has stood the test of time and IS SOLD WITH A GUARANTEE to give successful results.

ALL OUR PRODUCTS ARE NOW SUPPLIED IN FREE CONTAINERS

Lillington's
NO. 1 METALLIC LIQUID

From 5/- per gallon

(according to quantity)

Write for booklet '56'

GEORGE LILLINGTON & COMPANY LIMITED

WILLOW LANE, MITCHAM, SURREY, Phone: MITCHAM 1066

and for SCOTLAND, 42, HIGH STREET, GREENOCK


AP.55.261

At your Service almost



everywhere

FRANKI



S. RHODESIA POWER STATION



S. AUSTRALIA SULPHURIC ACID PLANT



IRAQ MURADIYAH BUILDING

ALGERIA
ARGENTINE
AUSTRALIA
AUSTRIA
BELGIUM
BELGIAN CONGO
BRAZIL
BRITISH E. AFRICA
BRITISH GUIANA
BRITISH W. AFRICA
BRITISH W. INDIES
CANADA
CEYLON
CYPRUS
DENMARK
EGYPT
EIRE
FINLAND
FRANCE
GERMANY
GREAT BRITAIN
HOLLAND
HONG KONG
INDIA
IRAQ
ITALY
LEBANON
MALAYA
MEXICO
MOZAMBIQUE
NEW ZEALAND
NORWAY
PORTUGAL
RHODESIA
SOUTH AFRICA
SPAIN
SWEDEN
SWITZERLAND
SYRIA
TURKEY
URUGUAY
U.S.A.
VENEZUELA

The Largest Piling Organisation in the World

THE FRANKI COMPRESSED PILE CO. LTD · 39 VICTORIA STREET · LONDON SW1 · CABLES: FRANKIPILE SOWEST LONDON

Another "first" for Johnson's Wire

CABLE BRIDGE, ISLE OF GRAIN


Sponsor :
South Eastern Gas Board.

Design :
S.E.G.B. Central Construction Department in collaboration with Simon-Carves Limited.

Contractors :
Sir Robert McAlpine & Sons Limited.

Johnson's Wire was chosen for this first application of BBRV prestressing in this country.

Pioneers of steel wire for prestressed concrete and the leading suppliers of wire for this purpose in Great Britain.



Prestressing cables in position, showing anchor heads.

Another successful application of wire by

Johnson's

— *Richard Johnson & Nephew Ltd., Manchester 11 Telephone : East 1431*

THE MODULAR CONCRETE CO LTD

are pleased to announce that they have been entrusted with the supply and manufacture of the structural pre-cast frame and flooring units in the new building for the

UNITED STATES EMBASSY

in Grosvenor Square,
London.



Architects:
Messrs. Eero Saarinen and Associates, Michigan, U.S.A., in association with Messrs. Yorke, Rosenberg and Mardall, 2 Hyde Park Place, W.2.

Consulting Engineers:
Messrs. Felix J. Samuely and Partners, 8 Hamilton Place, W.1.

Contractors for the excavation and reinforced concrete frame including erection of all precast concrete units:
Messrs. Wates Ltd.



THE
MODULAR CONCRETE
COMPANY LIMITED

THE MODULAR CONCRETE CO. LTD. *Precast Concrete Specialists*
STAINES ROAD · BEDFORD · MIDDLESEX. Telephone: Ashford (Middlesex) 5601-2
One of the Wates group of companies



CONCRETING *in cold weather*

Avoid delays during the winter by using
'417' CEMENT. Please write for a copy of the booklet
'Concreting in cold weather' which gives full details of

6⁶ 417⁹ cement


QUICK SETTING AND EXTRA-RAPID HARDENING



THE CEMENT MARKETING COMPANY LIMITED
PORTLAND HOUSE, TOTHILL STREET, LONDON, S.W.1

G. & T. EARLE LIMITED, HULL

THE SOUTH WALES PORTLAND CEMENT & LIME COMPANY LIMITED,
PENARTH, GLAM.



MARLEY CONCRETE

undertake

**PRECAST CONCRETE PROJECTS OF ALL SIZES
TO CONSULTING ENGINEERS' DESIGNS**

Opportunity to quote is always welcome

MARLEY CONCRETE LTD, Dept. 1221

Peasmash, Guildford, Surrey. Telephone : Guildford 62986/7
Shurdington, nr. Cheltenham. Telephone : Shurdington 334/5
Hatchpond Road, Waterloo, Poole, Dorset. Telephone : Broadstone 626
London Showrooms : 251 Tottenham Court Road, W.1

HYDRADUCT STEEL SHEATHING

A SPECIFIC FORM FOR EVERY REQUIREMENT

HYDRARIGID

HYDRAFLEX

CORRUDUCT

FOURSQUARE

LOCKTUBE

**WRITE OR TELEPHONE
FOR BROCHURE & PRICE LIST**



FOR FORMING DUCTS IN PRESTRESSED CONCRETE

HYDRADUCT
IS AVAILABLE
IN SECTIONS
SHOWN BELOW.



ANY OF THESE
SECTIONS CAN BE
SUPPLIED UP TO
18 SQ. IN. OR
LARGER, TO ORDER

HYDRADUCT tubing is the ideal and economical method of forming ducts for prestressing cables, and permanent installation such as electric wiring or piping, etc. Can be used by unskilled labour and requires no special apparatus.

DEPENDABILITY



GUARANTEED BY

STRENGTH


- EXTERNAL RIBS
- SMOOTH BORE
- STAYS PUT
- EXTREMELY LIGHT
- NO DISTORTION OF BORE
- NO FRAYED OR LOOSE ENDS
- EASILY BENT BY HAND
- IMMENSELY STRONG

CIVIL ENGINEERING PLANT LTD

52-54 HIGH HOLBORN, LONDON, W.C.1

HOLBORN 0131-2

DEEP MINE CONCRETING SIMPLIFIED



COLGROUT mixing plant at a South African Gold Mine.



A station cross cut 6,000 ft. below surface, lined with Colcrete constructed from surface.

At South African Gold Mines the concrete linings of tunnels, pump chambers and the construction of shaft sumps have been simplified by using uncrushed rock spoil injected with COLGROUT mixed at surface and passed down shafts up to 6,000 ft. deep through 1½" pipes.

Contractors : The Cementation Company (Africa) (Pty.) Limited.



The main pump chamber of a South African Gold Mine 6,000 ft. below surface and lined with Colcrete.

Colcrete methods can solve many Concreting Problems

COLCRETE LIMITED

STROOD • ROCHESTER • KENT
Phone Strood 78431/2/3. Grams : Groutcrete, Rochester



Roadworthy - - -

Also . . . approachworthy, runwayworthy, constructionworthy *wherever concrete is used*. In all cases, the word for jointing is—Crecel Expansion Jointing. Comprising a cellular-type non-extruding filler and a poured rubber-bitumen sealing compound, Crecel Jointing meets with the requirements of the Road Research Laboratory. In just one word Crecel is *specificationworthy*.



RUBEROID

ROAD MAKING MATERIALS


For technical literature write to:—

THE RUBEROID COMPANY LIMITED, 187 COMMONWEALTH HOUSE, 1-19 NEW OXFORD STREET, LONDON, W.C.1

fast working



smooth · strong




THE BOARD
YOU CAN
TRUST

WEYROCK

ONE OF THE WORLD'S GREAT MAN-MADE MATERIALS

THE AIRSCREW COMPANY & JICWOOD LTD · WEYBRIDGE · SURREY · TEL: WEYBRIDGE 2242/7



For compacting mortar cubes
for compression tests in

B.S.12/1958, 915/1947, 146/1958,
1370/1958.

Automatic control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD

BEACONSFIELD ROAD, LONDON, N.W.10

Phone: WILLESDEN 0067/8

Cables: CAPLINKO, LONDON

**WOOD
MOULDS**
for PRECASTING

EXTREME ACCURACY

**ALL
TYPES** | **ALL
SIZES**

25 years' experience at your service

ARCHITECTURAL SPECIALISTS
AND MODELMAKERS

LAWS & SON (STAINES) LTD
(CONTRACTORS TO H.M. GOVERNMENT)

Langley Road Works, Staines, Middx.

Telephone : Staines 3700

**Stainless
Steel**

TIE-WIRE

for

**RE-INFORCED
CONCRETE**

**STAINLESS STEEL
WIRE COMPANY LTD**

The Barracks
LANGSETT RD • SHEFFIELD 6
Tel: Sheffield 344241.


cubes

1958

"1

TD

LONDON



FORD POWER for industry

Ford industrial engines are a practical proposition for many industrial equipments . . . compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every Ford engine is fully backed by a World-wide Spare Parts Service Organisation.

Take your choice from a wide power range . . . Diesel 30 to 86 b.h.p. and Petrol 21 to 87 b.h.p. (12-hr. rating).

DIESEL ECONOMY—have you considered the replacement of existing power units in your equipment and trucks with the famous Ford 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs . . . plus the best service in the World !



Wherever you are, whatever your problem, we are at your service. For further details of



**INDUSTRIAL
ENGINES**

and the equipments they power, contact your nearest Ford Dealer or write to

Testing concrete cubes on site


MILBANK-WELLS

HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

£235

4-IN. PRESS
110 TONS


£120

MILBANK FLOORS LTD


PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



PRESTRESSED FLOORS & ROOFS SPANS UP TO 40'
FRAME BUILDINGS ALL TYPES



THE MOST ADAPTABLE FRAME BUILDINGS
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN · MULTI SPAN · CANTILEVER



An Electrically Driven PC3 Concrete Pump with mixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically indefinite : all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

The CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546

Telegrams : Pumpcret, Kens, London

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

96 Victoria Street, Westminster, S.W.1

Telephone:
VICTORIA 7877 and 6275

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.




ALEX J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone : FAILsworth 1115/6

DS.14

borsari TILE-LINED CONCRETE TANKS



for
storage of
fuel oil
diesel oil
petrol
and
industrial
liquids

We invite inquiries for the construction of tile-lined concrete storage tanks of any shape, size or capacity, in any part of the world. These tanks require no lagging and no maintenance, and have been in use for over 50 years. Many references available in the United Kingdom and on the Continent. Immediate attention given to all inquiries. Estimates and representative's visits free of charge and without obligation. Full details supplied on request.

BORSARI & CO

ZOLLIKON-ZURICH
SWITZERLAND
ESTABLISHED 1873


LENSCRETE

GLASS AND FERRO-CONCRETE

CANOPIES
ROOF
LIGHTS
ETC.

LENSCRETE LTD.

66 QUEEN'S CIRCUS, LONDON, S.W.8
TELEPHONE : MACAULAY 1063



Porte Cochere, Savoy Hotel, London.
Architects: Messrs. Thurlow, Lucas & Janes



PIN YOUR FAITH
TO THE TESTED
BRAND

THIS LABEL ON
EVERY BARREL
CARRIES WITH
IT FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

NONE OTHER IS
"JUST AS GOOD"

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

'Grams: "Grease."

STORERS

W.M. T. STORER & Co. LTD.

TIMBER IMPORTERS AND MERCHANTS

Established 1913



Sawing and Planing Mills:

RIVER ROAD, BARKING, ESSEX

Telephone : RIPpleway 0301 (10 lines)

FOR

SOFTWOOD

Proceedings of the
SECOND CONGRESS OF THE F.I.P.
INTERNATIONAL FEDERATION OF
PRESTRESSING
held in Amsterdam, 1955
NOW AVAILABLE

This volume includes 42 papers presented to the Congress by some of the world's leading authorities on the subject. The papers are given in full, together with the discussions and contributions, with many illustrations. The principal subjects dealt with are:

Effect of grouting and anchorages on the behaviour of prestressed members.

The results of experience in the production and use of prestressing steel.

Progress in the production of prestressed precast members in factories.

Prestressing of precast units on construction sites.

Redistribution of moments in prestressed statically - indeterminate structures loaded beyond the elastic stage.

Influence of plasticity on the strength and stability of thin prestressed shells.

Analysis of practice in prestressed concrete in various countries.

Economical advantages of prestressed concrete.

Method of direct reading of the loss of stress due to creep.

The economies of prestressed pressure pipes.

Prestressed arches.

Industrial structures in prestressed concrete.

The use of expansive mortar for prestressing.

Beams subjected to bending and torsion.

ONE THOUSAND PAGES

ORDER FORM

To
CONCRETE PUBLICATIONS, Ltd.,
14 DARTMOUTH STREET,
LONDON, S.W.1, England.

BLOCK CAPITALS PLEASE

NAME

ADDRESS

.....

.....


Please send* copy/copies of
Proceedings of the Second Congress of
the International Federation of Pre-
stressing (F.I.P.)

* £5 2s. 6d. by post. 20 dollars in Canada
and U.S.A.

A remittance for is enclosed.

Remittances from Canada and U.S.A.
may be made in the ordinary way by drawing
a check on the customer's bank made
payable to Concrete Publications, Ltd., in
dollars and cents or by International Money
Order obtainable at a Post Office.

RAWLTIES



FULLY ILLUSTRATED COMPREHENSIVE TECHNICAL BROCHURE

If concrete is your business you will find this latest Rawlplug Company publication (Ref: R1438) of great value and interest. It is packed with practical, down-to-earth information on shuttering problems, together with details of Rawlties, Rawloops and Rawlhangers. May we send you a copy? Apply on your letter-heading, send business card or state trade or profession.

**Write for your
copy NOW!**

Here you see how easily and quickly formwork is erected with Rawlties. Shuttering is fixed or removed in a matter of minutes —you need no struts after the first lift! No through bolts either —Rawltie bolts and cones are used over and over again. Whenever you use formwork, save time, timber and money by using Rawlties, Rawloops (for reinforced and taper walls) or Rawlhangers (when laying floors, solid or precast).




**THE RAWLPLUG CO. LTD.
CROMWELL ROAD, LONDON, S.W.7**



BOLTS & NUTS

TIE-RODS
ETC.

FOR THE
CONTRACTOR



Manufactured by

B. PRIEST & SONS LTD. OLD HILL, STAFFS, ENGL.

PHONES: CRADLEY HEATH 6227-8-9 & 6220

Reinforced Concrete

DESIGN AND CONSTRUCTION

Floors

IN SITU AND PRECAST

Cast Stone

AND PRECAST CONCRETE

Granolithic Pavings

Staircases

IN SITU AND PRECAST

STUART'S GRANOLITHIC CO. LTD.

FOUNDED 1840

LONDON

14 College Road, Harrow, Middlesex.
Telephone: Harrow 6161/2.

BIRMINGHAM

Northcote Road, Stechford.
Telephone: Stechford 3631/2.

EDINBURGH

46 Duff Street.
Telephone: Edinburgh 61506.

MANCHESTER

Ashton Road, Bredbury, Stockport.
Telephone: Woodley 2677/8.



INTERESTING & INFORMATIVE FILMS ON LOAN

showing with sound commentary
actual methods in typical installations using
**THE LEE-MCALL SYSTEM
OF PRESTRESSING CONCRETE**

PRESTRESSED CONCRETE OVER TAMPA BAY

The construction of a bridge 3½ miles long over Tampa Bay, Florida; prestressing and placing of 2178 beams 48 ft. long is described. 16 mm colour, 800 ft. (20 mins), optical sound, suitable for any standard projector.

LEYTON MARSHES CULVERT

Casting and placing of 516 beams, 57 ft. long, for culvert diverting R. Lee. 16 mm black and white, optical sound; 650 ft. (27 mins), suitable for any sound projector at 16 frames per sec. This film is also available with a magnetic sound track, and as a silent film.

BRIDGE OVER THE RIVER DON

A single track railway bridge of 160 ft. span, cast in situ. 16 mm black and white, optical sound track, suitable for any sound projector at 16 frames per sec. 450 ft. (19 mins).

MAHI BRIDGE

Showing the casting, curing, prestressing and launching of 110 ft. long beams in a 16-span river crossing. 16 mm, colour, with optical sound track playing at 16 frames per sec. 702 ft. (29 mins).

CADEBY COLLIERY BRIDGE

Construction of a 140 ft. single span through-type bridge using existing bridge as an aid to construction. 16 mm, colour, optical sound track playing at 16 frames per sec. 570 ft. (24 mins).

The above films are available free on loan to professional and technical societies, colleges, student groups and others interested in methods of prestressed concrete construction. Early application is desirable, giving if possible a choice of dates, to:

MCALLS MACALLOY LIMITED TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 9428 PORTSMOUTH: COSHAM 78792
BIRMINGHAM: ACOCKS GREEN 0229 NEWCASTLE: 38793

MCALL & COMPANY (SHEFFIELD) LIMITED

MCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

MCALLS MACALLOY LIMITED

MCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

PRECISION ROOFS LIMITED

MCALLS MACALLOY (CANADA) LIMITED

PRESTRESSING
STEEL
by MCALLS

The
LEE-MCALL SYSTEM

PC52 b

GLASCRETE

at


St. Basil's Church

BASILDON

Architects

Messrs. Burles & Newton
A.A.R.I.B.A., A.M.T.P.I.

The entire natural lighting to this church is provided by Glascrete windows of which this end feature is an interesting example. Concrete Tracery to the baptistery and doorways further illustrates the adaptability of Glascrete.



J. A. KING & CO LTD
181 QUEEN VICTORIA STREET
LONDON, E.C.4. CEN. 5866

ABELSON for SKIPS




Circular tipping skips 2½ cu. ft. to 2 cu. yd.




Concrete pouring skip side discharge 10 cu. ft. to 27 cu. ft.




Circular controlled discharge bottom dump skips ½ cu. yd. to 1 cu. yd.



Square tunnelling or trench skips 4-1/2ths cu. ft. capacity



Roller skips ½ cu. yd. capacity.



Boat skips 3 cu. ft. to 7 cu. ft.

Special and non-standard skips manufactured to your specifications.




Concrete pouring skips bottom discharge 10 cu. ft. to 27 cu. ft.

ABELSON
& CO. (ENGINEERS) LTD.

SHELDON
BIRMINGHAM 26

TEL: SHELDON 2424 (10 lines)



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENSington 3583

the ideal
underlay
and overlay

**CHAPMAN'S
WATERPROOF
CONCRETING
PAPER**

Chapman's Concreting Paper conforms to British Standard. Deliveries can be made from stock at short notice. Samples and prices are available on request.

H. W. CHAPMAN LTD.

THE EMBANKMENT • WELLINGBOROUGH • NORTHANTS

TELEPHONE: WELLINGBOROUGH 2214

STENT

PRECAST CONCRETE

PILES

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used.

AVAILABLE FOR IMMEDIATE DELIVERY

May we forward full details

STENT PRECAST CONCRETE LTD. Chequers Lane, Dagenham Dock, Essex.

Telephone: DOMINION 0971 (4 lines)

GUNITE

SPECIALISTS

W.M. MULCASTER

& CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings for new or old structures of every kind in any part of the country.

HASLINGTON

Telephone: Crewe 2265-6.

CREWE

CUT YOUR CONCRETE COSTS

with the

A.B. MOULD MIXER-DRIVE SHOVEL

ALL BRITISH DESIGN AND MANUFACTURE

(Patent applied for)

At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

THE BUILT-IN JIB ELIMINATES
SITE INSTALLATION COSTS.



LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS
NO RUNNING COSTS
FITTED TO MOST MIXERS

Ask for a demonstration from :

A. B. MOULD & CONSTRUCTION CO., LTD.

VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
POOLS, ETC.



LININGS
FOR
TUNNELS,
SEWERS,
TANKS.

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

Telegrams :
Gunite
Hitchin



Telephone :
Hitchin
4371

Best Quality
CONCRETE
AGGREGATES
in all grades

DELIVERED BY ROAD OR RAIL

WM. BOYER
& SONS LTD

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W2

TELEPHONE : PADDINGTON 2024-6

**TABLES FOR THE DESIGN OF BEAMS AND
SLABS ACCORDING TO B.S. CODE OF PRACTICE
No. 114, 1957**

In response to many requests, the article and tables by Mr. Jacques S. Cohen, in this journal for August, 1957, have been reprinted together with an additional table. These tables enable any rectangular section to be quickly designed by both the elastic method and the load-factor method, and the relative economy of the results of each method of design can be seen at a glance. The price of the reprint is 4s. (4s. 3d. by post); 1 dollar in Canada and the U.S.A.

CONCRETE PUBLICATIONS, LTD., 14 Dartmouth Street, London, S.W.1

Our
pigeon is
'joints-that-move'



A problematic 'pigeon', these 'joints-that-move'—one known only too well to builders and civil engineers and one in which Expandite Limited are specialists. For nearly a quarter of a century joint-filers and sealing compounds have been manufactured by Expandite Limited to meet every specialised requirement.

Allied 'pigeons'—damp-prevention, cold galvanising, weather-proofing, the manufacture of concrete additives as well as mechanical appliances—these too have been taken in hand by Expandite Limited. If you're in the least perplexed by tough birds of this sort — wherever a joint needs filling or a gap needs sealing, specify EXPANDITE PRODUCTS.

PLI-ASTIC * Hot-poured Rubber-Bitumen Joint Sealing Compound

A black compound with strong adhesion of concrete and is an excellent top sealer for use with FLEXCELL. For concrete coloured joint seals, ELASTITE is recommended.

FLEXCELL * Non-Extruding Joint Filler for Expansion Joints

Contains sugar cane fibre and is impregnated with a bituminous composition. Recovers to over 70% of thickness after compression. For expansion joints in all structures.

SEELASTIK * All-purpose Flexible Sealing Compound

Ideal for airtight, weatherproof seals where movement may occur. Adheres strongly and forms a surface skin which may be painted. In cream or colours.

PLASTIJPOINT Bituminous Putty for Vertical or Inclined Joints

Adheres strongly to most clean, dry surfaces and does not require accurately formed sealing cavities. Good resistance to dilute mineral acids and alkalis.

* Registered Trade Marks. † Specially manufactured by Celotex Ltd.

EXPANDITE
LIMITED

Chase Road, London, N.W.10.

Tel: ELGar 4321 (10 lines)

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD



Illustrated by courtesy of British Railways (Southern Region)

Bridge by **WESTWOODS**

TWICKENHAM FLYOVER. This bridge is curved in plan, and each of the three spans was completely welded at works and delivered by road and rail to the site. Max. length 75 ft., width 15 feet.

JOSEPH WESTWOOD & CO. LTD.

Contractors to H.M. Government Departments, Crown Agents for the Colonies, British Railways (British Transport Commission) etc. etc. Bridge and Constructional Engineers, Manufacturers of Mechanical Grabs, Pressed Steel Troughing and Sheet Metal Equipment. Steel Stock Holders.

NAPIER YARD, MILLWALL, LONDON, E.14. Tel.: EAST 1043

CONCRETE IN SULPHATE- LADEN SOILS

**To eliminate risk
CIMENT FONDU
SHOULD BE USED**

**To ensure
complete protection
CIMENT FONDU
MUST BE USED**

**Concrete
made with
CIMENT FONDU is
COMPLETELY IMMUNE
from the effects of
SULPHATES
in any concentration**

Concrete made with Ciment Fondu provides an additional margin of safety. It is also resistant to attack by dilute acids often prevalent in sulphate-bearing clays, made-up ground and many industrial effluents.



*Send for leaflet TSS-16 "The Influence of Mineral Sulphates on the Permanence of Concrete Structures."

LAFARGE ALUMINOUS CEMENT COMPANY LTD., 73 Brook St., London, W.1. Tel: MAY 8546

AP/69

For Stressed Concrete Ducts—


The New

'LOCKED RIB' KOPEX

PLIABLE STEEL TUBING

(Patent applied for)

Rib formation are locked to give increased strength during handling.



KOPEX Pliable Steel Tubing in position.



KOPEX Pliable Steel Tubing is supplied in coils or drums for easy transportation and handling on site.

Recommended by Stressed Concrete Consultants, and supplied to all leading Civil Engineering Contractors. Approved for the Lee-McCall, Freyssinet, Gifford-Udall and other systems.

UNI-TUBES LTD

Head Office: 1/2 LANGHAM PLACE, LONDON, W.1.
Tel: LANGham 6807/8/9.


Works: Alpha Street, Slough, Bucks.
Tel: SLOUGH 25476/7/8



- KOPEX Tubing used in the fabrication of concrete piles.
- General view of pile cages assembled with KOPEX Tubing in position.
-

This
a f
exc
toge
driv
ava
valu
det
on

Ag
Birm
W. A



**200
cycles
INTERNAL VIBRATORS
without flexible drives**

ALLAM

Now fitted with overload and anti-single-phase switches.

This new internal vibrator dispenses with the use of flexible drives. It has a frequency of 12,000 r.p.m. which, combined with amplitude, provides exceptional compaction of very harsh mixes. Vibrators of varying sizes, together with single- and multi-tool generators (Petrol, Diesel, and Electric drives), make this the most versatile range of internal vibrators so far available. It is in full production, and has already proved of considerable value to Contractors, Builders, and Precast Concrete Makers. Complete details of these and the range of Allam Vibrating Equipment will be sent on request.

E·P·ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1.


Telephone: Sloane 9976 (5 lines)

SCOTLAND: 39 Cavendish St., Glasgow, C.S.

Tel.: South 0186

Works: Southend-on-Sea **Tel.:** Eastwood 55243

Agents and Distributors : Strangford Ltd., Belfast and Dublin ; A. Gunn & Co. Ltd., Altrincham, Cheshire ; Kwikform, Ltd., Birmingham ; O. L. Davies, Ltd., Port Talbot, Glam. ; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent ; W. A. Stansby Ltd., Middlesbrough ; G. B. Corner & Son, Leeds ; W. R. Selwood, Ltd., Chandler's Ford, Southampton ; Henton & Chattell, Nottingham.



Fully automatic weighing



Complete portability



Fully proved on hundreds of sites, the Portasilo is the most highly developed, fully portable equipment in the world for handling cement in bulk. The unique Pullwey Mechanical Cement Man provides fully automatic weighing of the cement, without which the full saving of using cement in bulk cannot be achieved. The use of the Portasilo readily effects a saving of 20/- and over per ton of cement used.

there's nothing like the

PORTASILO
REGD.

PORTASIL

Covered by patents or patent applications in Great Britain and the Principal countries of the world

CONTRACTORS PLANT DIVISION: CORONATION ROAD • PARK ROYAL • LONDON N.W.10 • Telephone ELGAR 3726
HEAD OFFICE: YORK AND AT BIRMINGHAM • MANCHESTER • GLASGOW • BRISTOL • BELFAST • DUBLIN

The case for an advisory service...



In the last 12 months Stuart B. Dickens products have been used on many major contracts involving concrete constructions all over the world.

In the same year S.B.D. technical staff have travelled more than 500,000 miles to sites in South Africa, Belgian Congo, India, the Middle and Far East as well as all over the United Kingdom. The S.B.D. Advisory Service is competent, practical and comprised of qualified technical men.

It is free to companies with specific concrete problems and includes where necessary the preparation of complete specifications including quantity estimates.

STUART B. DICKENS "

Manufacturers of the

"*Sternson*"
Range

STERNSON NO. 205 Transparent Surface Waterproofer.

STERNSON NO. 300 Waterproofing for concrete, mortar.

STERNSON NO. 310 Accelerator, Hardener, Waterproofer.

STERNSON NO. 340 Accelerator, Hardener, Waterproofer.

STERNSON NO. 355 Quick-set Liquid.

STERNSON NO. 600 Metallic Jointing Material.

STERNSON NO. 610 Metallic Bonding Material.

STERNSON NO. 620 Metallic Hardener Material.

For complete information write :


36 Victoria Street, London, S.W.1. Tel: Abbey 4930 & 6157

Works: Manor Way, Boreham Wood, Herts.
Tel: Elstree 2211

SBD

STUART B. DICKENS LTD.

SPINNING PLANTS FOR CONCRETE transmission poles lighting columns and piles




CONSULT

A new pole plant embracing the most up-to-date methods of the centrifugal spun concrete process. This ALL-BRITISH design, and precisely constructed and infinitely variable-speed plant, enables you to produce with efficiency spun concrete products of a very high standard.

STELMO

*the most comprehensive
mould service in the world*

275 SHAKESPEARE ROAD • LONDON • S.E.24 Telephone: Brixton 4201



The VIBRO process is based on correct engineering principles and ensures the formation of piles of the precise length and size to suit the specified working loads.

The three Vibro plants shown above are forming 17" diameter piles varying from 60 to 70 feet in length, designed to carry working loads of 60 tons each.



VIBRO

CAST-IN-PLACE
REINFORCED
CONCRETE PILES

THE BRITISH STEEL PILING COMPANY LIMITED

HAYMARKET, LONDON, S.W.1



No two large-scale jobs involving concrete are ever exactly the same. Climatic conditions vary, the terrain differs, skilled labour may not be so readily available on one as on the other. And more and more specialist requirements are being called for. Stuart B. Dickens Limited have an Advisory Service available to anyone with a specific concreting problem. It is free, practical, down-to-earth and comprised of qualified men, knowledgeable in local climatic site and labour conditions. The service includes where required the preparation of complete specifications and quantity estimates.

and concrete...

"**Ritecure**

MEMBRANE CURING LIQUID


is an internationally famous S.B.D. Product which provides an impervious film to control evaporation throughout the 28-day curing period. RITECURE is complete in itself, and concrete treated needs no wetting down or covering.

It has been used on the following recent contracts: Berkeley & Bradwell Nuclear Power Stations, Gatwick Airport, Longton By-Pass and London Airport.

If you have a problem in concrete write or 'phone

SBD
STUART B. DICKENS LTD.

36 Victoria St., London, S.W.1. Tel: Abbey 4930 & 6157.
Works: Manor Way, Boreham Wood, Herts.
Tel: Elstree 2211.



333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth

Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

Write for Illustrated Brochure


SIMPLEX CONCRETE PILES LTD.

190 PALACE CHAMBERS,

BRIDGE STREET,

WESTMINSTER, S.W.1

Telephone : Trafalgar 1167-9



WIREWELD reinforcement is a high tensile steel fabric, manufactured from hard drawn steel wire electrically welded at all intersections to B.S. 1221, Part A. Made in oblong mesh and square mesh.

If you want to put steel into concrete,
get in touch with

G K N Reinforcements Ltd.

(FORMERLY TWISTEEL REINFORCEMENT LTD.)

197 KNIGHTSBRIDGE, LONDON, S.W.7 (KENSINGTON 6311)

SMETHWICK, BIRMINGHAM: Alma Street, Smethwick 40, Staffs. (Smethwick 1991) MANCHESTER: 7 Oxford Road, Manchester 1 (Ardwick 1691) GLASGOW: 30 Pinkston Road, Glasgow C.4 (Bell 2444) MIDDLESBROUGH: Dundas Chambers, Dundas Meus, Middlesbrough (Middlesbrough 3843) CARDIFF: 113 Cathedral Road, Cardiff (Cardiff 45220) BRISTOL: 16 Clare Street, Bristol (Bristol 21555) LEICESTER: Northampton House, Charles Street, Leicester (Leicester 25114) Works: CARDIFF, SMETHWICK, WIGAN & GLASGOW

Situations Wanted, 4d. a word : minimum, 7s. 6d. Situations Vacant, 5d. a word : minimum, 10s. Other miscellaneous advertisements, 5d. a word : minimum, 10s. Displayed advertisements, 35s. per column inch. Box number 1s. extra.

Advertisements must reach this office by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATION VACANT. Civil engineering draughtsman, with experience of reinforced concrete, required by consulting engineers, Westminster, for detailing bridges. High salary, good prospects, and pension scheme if required. Write, stating age and full details of experience, to Box 4534, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Assistant engineers and designer-draughtsmen required for varied and interesting work on reinforced concrete structures for industrial, commercial, medical and residential buildings. Five-days' week. Luncheon vouchers. Apply, with details of experience, and salary required, to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1.

SITUATIONS VACANT. Detailer-draughtsmen fully experienced required for reinforced concrete design department of reinforcement specialists. Permanent, superannuated positions. Good prospects for advancement. Five-days' week. Excellent working conditions in modern office with canteen. Write, stating experience, age, and salary required, to the SECRETARY, THE RON RIVER CO. LTD., 100 Stewart's Road, Battersea, S.W.8.

SITUATIONS VACANT. Consulting structural engineers require experienced reinforced concrete detailers and designer-detailers for variety of structures. High salaries paid to experienced men. Five-days' week, pension scheme. Applications in strict confidence, stating full details of experience, and salary required, to ALAN MARSHALL & PARTNERS, 73-74 High Holborn, London, W.C.1.

SITUATIONS VACANT. Reinforced concrete designers and detailers required for South London consulting engineer's office. Good salaries and prospects. Telephone Tate Gallery 8496.

SITUATIONS VACANT. Reinforced concrete designer capable of designing all classes of structures. Also reinforced concrete detailer capable of producing clear working details. Five-days' week, and non-contributory pension scheme. Near Victoria Station. Apply, stating experience and salary required, to THE INDENTED BAR & CONCRETE ENGINEERING CO. LTD., 171 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineer, Westminster, invites applications from designer/detailers and detailer-draughtsmen fully experienced in reinforced concrete. Salary scales appropriate to experience and ability. Non-contributory pension and bonus schemes in operation. Apply in writing, giving full particulars, to Box 4530, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Senior engineers, also detailers and draughtsmen, required for reinforced concrete department of London firm of consulting engineers. Interesting and permanent work. Box 4539, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

THE EXPANDED METAL COMPANY LTD.

Reinforced concrete designers and detailers required for permanent positions in London, West Hartlepool, Birmingham, and Manchester. Five-days' week. Staff pension scheme, etc. Apply in writing, giving brief details of experience, and salary required, to the Chief Engineer, THE EXPANDED METAL CO. LTD., 16 Caxton Street, London, S.W.1.

SITUATION VACANT. PETER LIND & CO. LTD., Civil Engineers and Contractors, Romney House, Tufton Street, London, S.W.1, require the services, in their drawing office, of a young civil engineer with three to four years' experience in the design of reinforced concrete structures. Candidates should apply in their own handwriting stating age, qualifications, and salary required.

SITUATIONS VACANT. OVE ARUP & PARTNERS have opened an office at 410 Royal Exchange, Manchester, 2, and have vacancies for several reinforced concrete designer/detailers with at least three years' experience. Please send particulars of education, qualifications and experience, when meetings will be arranged to discuss details and prospects of appointment.

SALES MANAGER

Reinforcing bar manufacturers and bar benders require experienced Sales Manager for London office. Must have excellent selling connections with precast concrete manufacturers and building contractors, etc. Good salary and bonus scheme. Excellent opportunity for right individual. Write in strictest confidence, giving full details of experience, to Box 4541, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

WORKS MANAGER

required for Concrete Works in the Midlands. Experience of Prestressed Concrete Production essential. An excellent opportunity to a big future for the right man. Apply, giving details of experience, and salary required. Box 4540, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

LONDON COUNTY COUNCIL ARCHITECT'S DEPARTMENT

Vacancies for ENGINEERING ASSISTANTS (up to £800) and ENGINEERS, Grade III (up to £1,000) in:-

(a) *Structural Engineering Division*—Extensive programme includes multi-story flats, schools, offices, warehouses and other buildings, and

(b) *District Surveyors' Service* in districts coinciding, with one exception, with Metropolitan Borough boundaries. Work mainly outside involving negotiations with architects, engineers, and surveyors, and supervision of works in progress. Good prospects in both of these aspects of the Council's work.

Application form and particulars from HUBERT BENNETT, F.R.I.B.A., Architect of the Council (ref. AR/EK/33/58), The County Hall, London, S.E.1. (2169.)

SAVE TIME IN THE DESIGN OF COLUMNS

DESIGN OF ECCENTRICALLY-LOADED COLUMNS BY THE LOAD-FACTOR METHOD

By J. D. BENNETT

TWENTY CHARTS

for the rapid design, according to the recommendations of British Standard Code of Practice No. 114:1957, of any column subjected to direct load and bending about one axis of symmetry.

EXAMPLES show the application of the method to columns reinforced with mild steel or cold-worked bars and with symmetrical or unsymmetrical reinforcement.

The simplicity of the method makes it possible to prepare several alternative designs in a few minutes.

This is a reprint of articles published in "Concrete & Constructional Engineering" for November and December 1957 and March and May 1958.

ORDER FORM

To

CONCRETE PUBLICATIONS, Ltd.,
14 DARTMOUTH STREET,
LONDON, S.W.1, England.

BLOCK CAPITALS PLEASE

NAME

ADDRESS

Please send * copy/copies of

"Design of Eccentrically-loaded

Columns by the Load-factor Method."


.....

.....

*Price 8s. ; 8s. 6d. by post. 1.90 dollars in
Canada and U.S.A.

Remittances from Canada and U.S.A.
may be made in the ordinary way by drawing
a check on the customer's bank made
payable to Concrete Publications, Ltd., in
dollars and cents, by International Money
Order obtainable at a Post Office, or by
bills and coins.

A remittance for is enclosed.

ONE...**TWO!**

'STABIL' BINDERS ARE GREAT LABOUR SAVERS

In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{4}$ -inch up to $\frac{1}{2}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD.

DEBURGH RD., S. WIMBLEDON, S.W.19

Phone: Liberty 2446

U.S.A.
drawn
made
etc., in
Money
or by

SITUATIONS VACANT. AIR MINISTRY Works Design Branch requires in London structural engineering designer/draughtsmen for reinforced concrete or structural steelwork, with sound technical training and several years' varied experience in design/detailing of (a) Reinforced concrete construction of all types of buildings or (b) Steel frame sheds, warehouses and similar buildings. Salaries up to £1015 per annum. Starting pay dependent on age, qualifications and experience. Long-term possibilities with pensionable and promotion prospects. 5 days' week, 3 weeks' 3 days' leave a year. Normally natural born British subjects. Write stating age, qualifications, employment details including type of work done, to any Employment Exchange, quoting Order No. BOROUGH 101.

SITUATION VACANT. Reinforced concrete designer-draughtsman of intermediate standard required for drawing office at Mitcham. Good salary and prospects, and opportunity to work on own initiative. Telephone Mitcham 3000.

SITUATION VACANT. Assistant site engineer required for bridge contract in the Southend area. Recently-graduated candidates eligible, provided they have experience of surveying. Apply in writing to PETER LIND & CO. LTD., Romney House, Tufton Street, London, S.W.1.

SITUATIONS VACANT. London drawing office requires draughtsmen for reinforced concrete and general civil engineering work. Applicants who are studying to become engineers will be considered. Only those with previous experience of this work in this country need apply. 5-days' week, Canteen. Apply GEORGE WIMPEY & CO. LTD., 27 Hammersmith Grove, London, W.6.

SITUATIONS VACANT. Civil Engineer Designers required in London office for some specialised reinforced concrete work and for industrial and general civil engineering design. University degree and three years' experience desirable. Apply GEORGE WIMPEY & CO. LTD., 27 Hammersmith Grove, London, W.6.

SITUATION VACANT. Reinforced concrete designer-draughtsman to work in engineer's office near Finchley Road Station. Excellent prospects for competent man in small concern. Box 4542, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Structural engineer required by firm specialising in precast reinforced and prestressed concrete. Previous experience and ability to take charge of small design group essential. Salary in range £1000 to £1250. Write to REED & MALLIK LTD., Millord Manor, Salisbury, Wilts.

SITUATION VACANT. Reinforced concrete detailer-draughtsman required. Familiar with L.C.C. Bye-Law requirements, and preferably with experience in frame structures. Five-days' week, pension scheme, and luncheon vouchers. Apply to E. J. COOK & CO. (ENGINEERS) LTD., 54 South Side, Clapham Common, London, S.W.4.

SITUATIONS VACANT. Consulting civil and structural engineers urgently require first-class designer-detailers for varied work on reinforced concrete and structural steelwork. Five-days' week and luncheon vouchers. Apply by letter or telephone to MAURICE NACHSHEN & PARTNERS, 58 Victoria Street, London, S.W.1. Victoria 0255.

SITUATION VACANT. Reinforced concrete designing draughtsman, producing tidy calculations and details, wanted to lead section. Good prospects. Fullest details to M. M. KHAN, B.Sc., M.I.C.E., 88 Rochester Row, London, S.W.1. Victoria 0838.

NORTH WEST METROPOLITAN REGIONAL HOSPITAL BOARD

CLERK OF WORKS (ASSISTANT) required to assist in supervision of new Welwyn/Hatfield Hospital, Hatfield, Hyde, Herts. Applicants should have experience of reinforced concrete work and will be required initially to assist Resident Engineer. Appointment will start from March or April 1959 and is expected to last for at least two years.

Salary £750 per annum.

APPLY, giving age, qualifications and experience, with names of two referees (preferably employers), to Secretary, North West Metropolitan Regional Hospital Board, 40 Eastbourne Terrace, London, W.2, quoting reference 683, by 29th December.

CONCRETE SERVICES LIMITED

DESIGNER/DRAUGHTSMAN experienced in structural reinforced concrete work required for interesting post with progressive and growing firm specialising in the design and erection of concrete structures.

Applicants, preferably aged 25-35 and of H.N.C. standard in Structural or Civil Engineering, must have the ability to work without close supervision. Knowledge of prestressed concrete would be an advantage.

This permanent progressive position offers a good salary, non-contributory pension scheme, superior staff conditions and assistance with housing. Applications in confidence, stating age, details of training, experience, and qualifications if any, availability and some indication of commencing salary required, should be addressed to:

MANAGING DIRECTOR,
CONCRETE SERVICES LIMITED,
Blue Bridge Lane,
York.

LONDON ELECTRICITY BOARD
DRAWING OFFICE JUNIOR

Applications are invited for the above position under the supervision of a Structural Engineer in the Construction Branch of the Chief Engineer's Department in central London (near Waterloo).

Applicants should be interested in structural engineering as a profession, and should preferably possess the General Certificate of Education with passes at Ordinary Level in English, Elementary Mathematics, one or two approved science subjects, etc.

The commencing salary within the General Clerical Grade of the National Joint Council Agreement (Administrative and Clerical Grades), i.e. £225 p.a. at age 16, rising thereafter within scale.

Application forms obtainable from Personnel Officer, 46 New Broad Street, London, E.C.2. Please quote ref.—PER/2220/DO.

CIVIL ENGINEER NUCLEAR POWER

Due to expansion in their
NUCLEAR POWER DIVISION

SIMON-CARVES LTD.

have a vacancy for
A CIVIL ENGINEER

to work in the concrete research laboratory at Cheadle Heath on experimental investigation of structural features of nuclear power stations. Applicants must hold a 1st or 2nd class Hons. Degree in Civil Engineering or the equivalent. Some design experience on heavy reinforced concrete structures is essential. Experience in relevant experimental work would be an advantage. This position is permanent and pensionable. Starting salary according to qualifications and experience.

Send brief relevant details to Staff & Training Division, SIMON-CARVES LTD., CHEADLE HEATH, STOCKPORT, CHESHIRE, quoting ref. CQ. 59.

FOR SALE.

FOR SALE. Melamine plastic-faced resin-bonded plywood, waterproof exterior grade, recommended for use in the construction of, or linings for, moulds for precast concrete. In thicknesses $\frac{1}{2}$ in., $\frac{3}{8}$ in., $\frac{5}{8}$ in. Full particulars from J. & T. T. BROWN LTD., Stockton Street, West Hartlepool.

FOR SALE. Fielding hydraulic three-station concrete slab press. Rebuilt self-contained pumping unit. Fielding two-station concrete slab press. Rebuilt with self-contained pumping units. REED BROTHERS (ENGINEERING) LTD., Replant Works, Woolwich Industrial Estate, London, S.E.18. Telephone Woolwich 2611-6.

FOR SALE. Steel plates and sections to size. Also tubes up to 10 in. N/B. E. STEPHENS & SON LTD., Bath Street, London, E.C.1. Clerkenwell 1713.

WANTED.

WANTED. Precast and prestressed concrete company covering Northumberland, Durham, Cumberland, and Westmorland, seeks additional products for manufacture under contract or licence. Design and sales facilities available. Box 4543, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

WANTED. Offcuts mild steel reinforcing bars always wanted in 2-ft. minimum lengths. Any quantity accepted. H. & J. R. SAUNDERS & CO. LTD., Hainault Road, London, E.11. Leytonstone 4383.

FOR HIRE.

FOR HIRE. Lattice steel erection masts (light & heavy), 30 ft. to 150 ft. high, for immediate hire. BURMAN, 21 Hobart House, Grosvenor Place, London, S.W.1.

RD
R

position
er in
neer's
loo),
ctural
erably
with
ntry
jects,

eneral
Agree-
, i.e.
scale.
sonnel
E.C.z.

com-
and,
manufac-
ties avail-
tional
W.I.

rs always
accepted
load, Le


light
Bus
s, S.W.I



Extra Tentor sizes!



Here they are!



These two new larger bar sizes mean that the Tentor range is now extended to cover the demands of nearly all concrete reinforcement jobs.

Consider the maximum tensile stress for Tentor Bars, now 30,000 lbs. (CP.114, 1957). That gives a saving of 15% of the cost of mild steel rounds. And the maximum compressive stress, now 23,000 lbs./sq.in., gives a cost for Tentor still generally less than that for mild steel bars. Deliveries are made to suit contract programmes cut to length or bent to schedules.

Stock service is available from London, Birmingham, Wigan and Sheffield.

TENTOR Regd. Trade Mark

Suppliers

B.R.C. STEEL LTD.,
Silkmore Lane, Stafford.
Stafford 444, and Branch Offices.

G.K.N. REINFORCEMENTS LTD.,
197 Knightsbridge, London, S.W.7.
KEN 6311, and Branch Offices.

McCALL & CO. (SHEFFIELD) LTD.,
P.O. Box 41, Sheffield.
Rotherham 2076, and Branch Offices.

STEEL, PEECH & TOZER LTD.,
Branch of the United Steel Companies Ltd.,
The Ickles, Sheffield.
Sheffield 41011, and Branch Offices.





The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford

8930

H-W.871

Published by CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1. Telephone: Whitehall 4518
Printed by BUTLER & TANNER LTD., The Selwood Printing Works, Frome and London

EMBER, 19

Stafford

M-W-87

tehall 458